



11244 Pyrites Way • Gold River, CA 95670
Phone 916 851 0174 • Fax 916 851 0177 • Toll Free 1 800 242 5249

April 20, 2005

Mr. Cliff Ives
Sonoma County Department of Health Services
Environmental Health Division
3273 Airway Drive, Suite D
Santa Rosa, California 95403-2097

Subject: **First Quarter 2005 Groundwater Monitoring and Remediation Status Report**
Rotten Robbie
7200 Healdsburg Avenue, Sebastopol, California
SCDHS Site #00001569 and NCRWQCB Site #1TS0244
Apex Project No. ERA02.005

Dear Mr. Ives:

Apex Envirotech, Inc. (Apex) has been authorized by Rotten Robbie (Robbie) to provide this report documenting groundwater monitoring and site remediation. This report covers groundwater monitoring activities from December 21, 2004, the last sampling event, through February 15, 2005, the current sampling event. Remediation status and sampling results obtained through March 16, 2005, the last site visit in this quarter, are also contained in this report. Groundwater monitoring and site remediation results are provided in the attached figures and tables. Apex standard operating procedures, field data, and analytical results are provided as attachments.

This report is based in part, on information obtained by Apex from Pit Stop, and is subject to modification as newly acquired information may warrant.

BACKGROUND

The site is currently an operating gasoline station with a car wash and food mart that retails unleaded gasoline, diesel fuel, and red dyed (off-highway) diesel fuel.

1988 - Four gasoline underground storage tanks (USTs) and associated piping were removed from the site. The former USTs were replaced by five double-walled steel tanks (T-1 through T-5). In November 1988, Delta Environmental Consultants, Inc (Delta) of Rancho Cordova, California, installed groundwater monitoring wells MW-1 through MW-4 on-site.

1989 - Delta installed additional groundwater wells MW-5 and MW-6 off-site and five vapor extraction wells VEW-1 through VEW-5 on site during the second quarterly monitoring event. In November 1989 the station was rebuilt. Product lines from the tanks installed in 1988 were replaced with new product lines. During the rebuild, vapor extraction well VEW-5 was properly abandoned to make space for the new dispenser islands.

March 29, 1990 - Aegis Environmental, Inc. (Aegis) of Roseville, California, installed an additional off-site groundwater monitoring well (MW-7).

February 1991 - Aegis began vapor extraction using a catalytic oxidizer for off-gas treatment. The unit operated sporadically until October 1991.

October 1992 - Aegis installed a vapor extraction system. This system began continuous operation in November 1992. The operation of this unit was discontinued in October 1993, in anticipation of a system with higher flow capacity.

August 1994 - Apex was retained as the consultant for the site. Apex submitted a report titled, *Corrective Action Plan (CAP)*, dated October 14, 1994. Apex began quarterly monitoring at the site in August 1994.

May 1995 - Dave's Pit Stop personnel, trained in the handling and management of petroleum products, began weekly floating liquid hydrocarbons (FLH) removal from well MW-4.

February 1996 - Apex submitted a workplan addendum proposing the advancement of two on-site Hydropunch® borings and modifications of one monitoring and one vapor extraction well. The modifications were proposed to facilitate soil and groundwater remediation.

September 30, 1996 - Apex supervised the drilling of two Hydropunch® borings and the enlargement of monitoring well MW-4 at the site. The results of the work were documented by Apex in the report titled, *Hydropunch Investigation, Well Modification, and Fourth Quarter 1996 Quarterly Groundwater Monitoring Report*, dated November 26, 1996.

April 1, 1997 - A PetroTrap® passive skimmer was installed in monitoring well MW-4. The skimmer was drained and monitored on a weekly basis by Dave's Pit Stop personnel. During the Second Quarter 1998 groundwater sampling event, free product was no longer observed in monitoring well MW-4. As a result, the skimmer was removed to assess FLH thickness. Free product was absent until November of 1998, at which time a free product thickness of 2.8 inches was observed. The skimmer was reinstalled in well MW-4 in January 1999 to recover any remaining FLH.

May 5, 1999 - Soil vapor extraction pilot testing was performed at the subject property to assess the post remedial status following the 1993 soil vapor extraction (SVE) operation.

May 12, 1999 - Apex submitted a report titled, *Final Remediation Plan and Second Quarter 1999 Groundwater Monitoring Plan (FRP)*, which outlined the corrective action for the site. Sonoma County Environmental Health (County) approved the FRP on June 21, 1999.

August 9, 1999 - Apex submitted a report titled, *Workplan for Well Modification/ Installation and Response to County Letter*, detailing the installation of five air sparge points and the conversion of two existing monitoring wells to SVE wells. The County conditionally approved the workplan in a letter dated December 22, 1999.

January 27, 2000 - Apex submitted a report titled, *Workplan Addendum for Well Modification/Installation and Response to County Letter*, detailing the installation of two new monitoring wells for the site. The County approved the Workplan Addendum in a letter dated March 27, 2000.

May 15 -19, 2000 - Apex supervised the installation of two groundwater monitoring wells (MW-8 and MW-9), modified two existing wells (MW-1 and MW-2) from two-inch to four-inch diameter wells, and installed four air sparge points. Results from the well installation and well modification are documented in the report titled, *Results Report for Well Installation/Modification, Second Quarter 2000 Groundwater Monitoring, and Addendum to the Final Remediation Plan Report*, dated August 9, 2000.

October 2, 2002 - The remediation system was installed and start-up occurred.

September 30, 2003 - Apex submitted a workplan, and on October 3, 2003, submitted a workplan addendum proposing the expansion of the remediation system and to remove contaminated soil from a dispenser pan and product line upgrade. On October 20, 2003, the County approved the workplan addendum in a letter.

November 11, 2003 - Apex submitted a workplan titled, *Monitoring Well MW-5 Destruction Recommendation and Workplan*, proposing the abandonment of well MW-5 due to future site development plans.

November 14, 2003 - Apex personnel supervised the upgrade of the dispenser pans and product lines at the site. Soil samples were collected from beneath the product lines at approximately 3 feet below ground surface (bgs).

December 12, 2003 - Apex supervised the abandonment of MW-5 by Woodward Drilling.

December 19, 2003 - Apex supervised the installation of three air sparge wells (AS-6, AS-7, and AS-8). The wells were drilled to 51 feet bgs. Groundwater was encountered at approximately 40 feet bgs and the 18" KVA sparge points were installed 10 feet below the groundwater table. The air sparge well filter pack was from 47.5 feet to 51 feet bgs, the bentonite seal was from 45.5 feet to 47.5 feet bgs, and neat cement was from 0 feet to 45.5 feet bgs.

January 2004 - Apex personnel connected the new air sparge wells to the sparge system with horizontal supply lines. Also, MW-4 was integrated into the SVE system as a vapor extraction point.

GENERAL SITE INFORMATION

Site name: Rotten Robbie
Site address: 7200 Healdsburg Avenue, Sebastopol, California
Current property owner: Robinson Oil Corporation
Current site use: Active gasoline station
Current phase of project: Groundwater monitoring and remediation
Tanks at site: Two 12,000 gallon gasoline, one 10,000 gallon gasoline, one 2,000 gallon red dyed diesel, and one 12,000 gallon diesel UST
Number of wells: 8 monitoring wells (7 shallow, 1 deep); 4 vapor extraction wells; 8 air sparge wells

GROUNDWATER MONITORING SUMMARY

Gauging and sampling date: February 15, 2005
Wells gauged and sampled: MW-1, MW-2, MW-3, MW-4, MW-6, MW-7, and MW-8 and MW-9
Wells gauged only: None
Groundwater flow direction: East
Groundwater gradient: 0.025 ft/ft
Floating liquid hydrocarbons: None
Laboratory: California Laboratory Services (CLS), Rancho Cordova, California

Analysis Performed:

Analysis	Abbreviation	Designation	USEPA Method No.
Total Petroleum Hydrocarbons as Gasoline	TPHg	Fuel-Range Hydrocarbons	8015M
Total Petroleum Hydrocarbons as Diesel	TPHd		
Benzene	BTEX	Aromatic Volatile Organics	8021B
Toluene			
Ethylbenzene			
Xylenes (Total)			
Methyl Tertiary Butyl Ether	MTBE	Fuel Oxygenates	8260B
Tertiary Amyl Methyl Ether	TAME		
Tertiary Butyl Alcohol	TBA		

Modifications from Standard Monitoring Program:

None

REMEDIATION SYSTEM SUMMARY

Thermal Oxidizer, Soil Vapor Extraction System, and Air Sparging System

The SVE system consists of a 150 standard cubic feet per minute (scfm) King, Buck brand thermal oxidizer, with a 7.5 horsepower (hp) positive displacement blower as a vacuum source, a liquid/vapor separator, and conveyance piping. Supplemental fuel for the treatment system is natural gas.

The air sparging system is a Becker brand "KDT" series oil-less rotary vane compressor, a 12 hp electric motor, eight sparge points with micro-porous bubblers, and conveyance piping.

System startup date: October 2, 2002
Active extraction wells: MW-1, and MW-4
Inactive extraction wells/reason: VEW-1, VEW-2, VEW-3, VEW-4, MW-2/
Due to low VOC concentrations

Modifications made during reporting period/reasons or modifications:

None

Status of system operation during reporting period/reasons for downtime:

The SVE system did not operate continuously during this reporting period. Apex personnel noted the system was shutdown for both visits in January 2005. The January 5th shutdown showed no alarm condition and the January 19th visit had a high level in the liquid knockout drum. Also, Apex personnel shut the system down in mid-February to install a point of use electric meter to monitor the specific amount of electricity being used for the remediation efforts onsite. The point of use electric meter was permitted with the city of Sebastopol and approved for use by Pacific Gas and Electric (PG&E). According to hour meter readings the system operated for approximately 67 days during this reporting period. Field data sheets for site visits performed during this quarter are included in Appendix B.

The air sparge system operated continuously during this quarter, with the exception of the shut down in mid-February 2005 for the new electric meter. Apex personnel shut the compressor off during one site visit and changed the rotary vanes in the compressor itself as part of a regular maintenance activity. The sparge system only operates 14 hours on and 10 hours off daily so nearby residences are not disturbed.

Analysis Performed:

Analysis	Abbreviation	Designation	USEPA Method No.
Total Petroleum Hydrocarbons as Gasoline	TPHg	Gas-Range Hydrocarbons	8260B
Benzene	BTEX	Aromatic Volatile Organics	8260B
Toluene			
Ethylbenzene			
Xylenes (Total)			
Methyl Tertiary Butyl Ether	MTBE	Fuel Oxygenate	8260B

Remediation system vapor samples were collected monthly and analyzed for the constituents listed above. All effluent samples were reported as non-detect for the analyzed constituents. Laboratory analytical reports are included in Appendix C.

System performance data: **This Quarter** **Cumulative**

Pounds of TPHg removed:	2,485	22,475 (approx. 3,567 gallons)
Pounds of benzene removed:	19	247
Pounds of MTBE removed:	0.5	13.5

CONCLUSIONS

Groundwater analytical results indicate the plume continued to be centered at well MW-4. Deep well MW-9 contained concentrations of TPHg, TPHd, BTEX, and MTBE. Concentrations at wells MW-3, MW-6 and MW-8 were below laboratory detection limits for all analyzed constituents.

Concentration of toluene was detected at well MW-7, historical results indicate that is most likely due to sampling or laboratory error.

The remediation systems influent concentrations have continued on a steady decline since operation began. As stated above, approximately 3,567 gallons of TPHg have been removed from the subsurface to date.

Groundwater isoconcentration maps depict the hydrocarbon plume in the shallow aquifer.

Groundwater elevations increased 1.75 feet this quarter compared with last quarter.

RECOMMENDATIONS

Quarterly groundwater monitoring should continue. The next sampling event is scheduled for May 2005.

As part of the continued remediation efforts at the site, Apex also recommends installing a groundwater treatment system and including wells MW-4 and MW-9 as groundwater extraction wells. Upon receipt of written concurrence from the County, Apex will prepare a workplan formally proposing a groundwater remediation system.

ATTACHMENTS:

Figure 1: Site Vicinity Map

Figure 2: Site Plan Map

Figure 3: Groundwater Contour Map: February 15, 2005

Figure 4: TPHg in Groundwater Isoconcentration Map: February 15, 2005

Figure 5: TPHe in Groundwater Isoconcentration Map: February 15, 2005

Figure 6: Benzene in Groundwater Isoconcentration Map: February 15, 2005

Figure 7: MTBE in Groundwater Isoconcentration Map: February 15, 2005

Table 1: Well Construction Details

Table 2: Groundwater Elevation Data

Table 3: Groundwater Analytical Data

Table 4: Historical Groundwater Elevation Data

Table 5: Historical Groundwater Analytical Data

Table 6: Soil Vapor Extraction Rate Calculations

Table 7: Thermal Oxidizer Destruction Efficiency and Emission Rate Calculations

Appendix A: Apex Standard Operating Procedures

Appendix B: Field Data Sheets

Appendix C: Laboratory Analytical Report and Chain-of-Custody Form

REPORT DISTRIBUTION

Apex submitted this report, in its final form, to the following:

Regulatory Oversight: Mr. Cliff Ives
Sonoma County Department of Health Services
Environmental Health Division
3273 Airway Drive, Suite D
Santa Rosa, California 95403-2097
(707) 565-4820

Mr. Luis Rivera
North Coast Regional Water Quality Control Board
5550 Skylane Blvd., Suite A
Santa Rosa, California 95403
(707) 576-2220

Mr. Robert Cave
Bay Area Air Quality Management District
939 Ellis Street
San Francisco, California 94109
(415) 771-6000

Responsible Party: Mr. Dave Zedrick
Dave's Pit Stop
P.O. Box 7010
Santa Rosa, California 95407
(707) 528-3677

Property Owner: Mr. Tom Robinson
Robinson Oil Corporation
4250 Williams Road
San Jose, California 95129

Mr. Ron Michelson
R.M. Associates
16401 Meadow Vista Drive #102
Pioneer, California 95666

REMARKS/SIGNATURES

The information contained in this report reflects our professional opinions and was developed in accordance with currently available information, and accepted hydrogeologic and engineering practices. This report was prepared solely for the use of Pit Stop. Any reliance on this report by parties other than Pit Stop shall be at their own risk.

The work described in the above report was performed under the direct supervision of a professional geologist, registered with the State of California, whose signature appears below.

We appreciate the opportunity to provide Pit Stop with geologic, engineering, and environmental consulting services, and trust this report meets your needs. If you have any questions or comments, please call us at (916) 851-0174.

Sincerely,

APEX ENVIROTECH, INC.




Richard Johnson
Remediation Department Manager



Michael S. Sgourakis, R.G.
Senior Project Manager
CRG No. 7194




FIGURES



0 0.25 0.50

Approximate Scale
1 inch = 0.25 miles



N

APEX	DRAWN BY: D. Alston
ENVIROTECH, INC.	DATE: 01/24/01
REVISIONS	


SITE VICINITY MAP

Pit Stop
7200 Healdsburg Avenue
Sebastopol, California


FIGURE

1

PROJECT NUMBER:
ERA02.005




HARRISON STREET




NOTE: MW-9 Is A Deep Zone Well
And Is Cased To 115 Feet.

HEALDSBURG AVENUE



Source: Figure Modified From Survey Provided By Morrow Surveying.

<p>APEX ENVIROTECH, INC.</p>	DRAWN BY:	D. Alston	<p>SITE PLAN MAP</p> <p>Dave's Pit Stop 7200 Healdsburg Avenue Sebastopol, California</p>	<p>FIGURE 2</p> <p>PROJECT NUMBER: ERA02.005</p>
	DATE:	4/7/04		
	REVISIONS			



Source: Figure Modified From Survey Provided By Morrow Surveying.

GROUNDWATER CONTOUR MAP, FEBRUARY 15, 2005



DRAWN BY: J. Curry
DATE: 03/25/05

REVISIONS

Rotten Robbie
7200 Healdsburg Avenue
Sebastopol, California

FIGURE
3

PROJECT NUMBER:
ERA02.005

LEGEND


- Air Sparge Well
- ◆ Monitoring Well
- ◇ Vapor Extraction Well
- ☒ Destroyed Well

(71,000) Concentration Of TPHg In Groundwater Measured In ug/L

-50,000- Line Of Equal Concentration Of TPHg In Groundwater Measured In ug/L; Dashed Where Inferred

(ND) Not Detected

NOTE: MW-9 Is A Deep Zone Well And Is Cased To 115 Feet.



Source: Figure Modified From Survey Provided By Morrow Surveying



DRAWN BY: J. Curry
DATE: 03/25/05

REVISIONS

TPHg IN GROUNDWATER ISOCONCENTRATION MAP, FEBRUARY 15, 2005

Rotten Robbie
7200 Healdsburg Avenue
Sebastopol, California

FIGURE
4

PROJECT NUMBER:
ERA02.005

LEGEND


- Air Sarge Well
- ◆ Monitoring Well
- ◇ Vapor Extraction Well
- ✗ Destroyed Well

(42,000) Concentration Of TPHd In Groundwater Measured In ug/L

- 5,000 - Line Of Equal Concentration Of TPHd In Groundwater Measured In ug/L; Dashed Where Inferred

(ND) Not Detected

NOTE: MW-9 Is A Deep Zone Well And Is Cased To 115 Feet.



 APEX ENVIROTECH, INC.	DRAWN BY:	J. Curry	TPHd IN GROUNDWATER ISOCONCENTRATION MAP: FEBRUARY 15, 2005	FIGURE
	DATE:	03/25/05		5
	REVISIONS			PROJECT NUMBER:
				ERA02.005
Rotten Robbie 7200 Healdsburg Avenue Sebastopol, California				


LEGEND

- Air Sparge Well
- ◆ Monitoring Well
- ◇ Vapor Extraction Well
- ✖ Destroyed Well
- (1,600) Concentration Of Benzene In Groundwater Measured In ug/L

-500- Line Of Equal Concentration Of Benzene In Groundwater Measured In ug/L; Dashed Where Inferred

(ND) Not Detected

NOTE: MW-9 Is A Deep Zone Well And Is Cased To 115 Feet.



HEALDSBURG AVENUE

0 60 120

Approximate Scale
1 inch = 60 feet

Source: Figure Modified From Survey Provided By Morrow Surveying.



DRAWN BY: J. Curry
DATE: 03/25/05

REVISIONS

BENZENE IN GROUNDWATER ISOCONCENTRATION MAP: FEBRUARY 15, 2005

Rotten Robbie
7200 Healdsburg Avenue
Sebastopol, California

FIGURE
6

PROJECT NUMBER:
ERA02.005


LEGEND

- Air Sparge Well
- ◆ Monitoring Well
- ◇ Vapor Extraction Well
- ※ Destroyed Well
- (42) Concentration Of MTBE In Groundwater Measured In ug/L

- 5 -
Line Of Equal Concentration Of MTBE In Groundwater Measured In ug/L; Dashed Where Inferred

(ND) Not Detected

NOTE: MW-9 Is A Deep Zone Well And Is Cased To 115 Feet.



HARRISON STREET

Parking Lot

(ND)
MW-7

Planter

HEALDSBURG AVENUE

(ND)
MW-8



0 60 120
Approximate Scale
1 inch = 60 feet

Source: Figure Modified From Survey Provided By Morrow Surveying.



DRAWN BY: J. Curry
DATE: 03/25/05

REVISIONS

MTBE IN GROUNDWATER ISOCONCENTRATION MAP: FEBRUARY 15, 2005

Rotten Robbie
7200 Healdsburg Avenue
Sebastopol, California

FIGURE
7

PROJECT NUMBER:

ERA02.005

TABLES

TABLE 1
WELL CONSTRUCTION DETAIL
 Rotten Robbie
 7200 Healdsburg Avenue
 Sebastopol, California

Well Number	Well Installation Date	*Elevation TOC (feet)	Casing Material	Total Depth (feet)	Well Depth (feet)	Casing Diameter (inches)	Screened Interval (feet)	Filter Pack Interval (feet)
Shallow Wells								
MW-1	upgraded May-00	100.83	PVC	46	45	4	15 - 45	13 - 46
MW-2	upgraded May-00	102.35	PVC	50	50	4	15 - 50	13 - 50
MW-3	Nov-88	103.21	PVC	—	—	2	—	—
MW-4	9/30/96 enlarged	101.76	PVC	—	—	4	—	—
MW-5	2nd qtr 1998	102.5	PVC	—	—	2	—	—
MW-6	2nd qtr 1998	117.18	PVC	—	—	2	—	—
MW-7	3/29/1990	99.71	PVC	—	—	2	—	—
MW-8	5/17/2000	97.62	PVC	45	45	2	25 - 45	23 - 45
Deep Well								
MW-9	5/15/2000	100.55	PVC	115	115	2	82? - 115	80? - 115
Vapor Extraction Wells								
VEW-1	2nd qtr 1998	—	PVC	—	—	4	—	—
VEW-2	2nd qtr 1998	—	PVC	—	—	4	—	—
VEW-3	2nd qtr 1998	—	PVC	—	—	4	—	—
VEW-4	2nd qtr 1998	—	PVC	—	—	4	—	—
Air Sparge Wells								
AS-2	5/16/2000	—	PVC	40	39	1	N/A	35 - 40
AS-2	5/16/2000	—	PVC	50	49	1	N/A	45 - 50
AS-3	5/16/2000	—	PVC	40	39	1	N/A	35 - 40
AS-3	5/16/2000	—	PVC	50	49	1	N/A	45 - 50
AS-4	5/16/2000	—	PVC	40	39	1	N/A	35 - 40
AS-4	5/16/2000	—	PVC	50	49	1	N/A	45 - 50
AS-5	5/16/2000	—	PVC	40	39	1	N/A	35 - 40
AS-5	5/16/2000	—	PVC	50	49	1	N/A	45 - 50

Notes:

* = surveyed by Morrow Surveying to mean sea level 10/01

— = Information not found

TOC = Top of Casing

PVC = Polyvinyl Chloride

TABLE 2
GROUNDWATER ELEVATION DATA
Rotten Robbie
7200 Healdsburg Ave., Sebastopol, CA
(All measurements in feet)

Monitoring Well	Date	Reference Elevation (top of casing)	Depth to Groundwater (feet)	Groundwater Elevation (feet)	Groundwater Flow Direction
Shallow Wells					
MW-1	2/15/05	100.83	34.12	66.71	E
MW-2	2/15/05	102.35	45.19	57.16	E
MW-3	2/15/05	103.21	11.41	91.80	E
MW-4	2/15/05	101.76	42.78	58.98	E
MW-5	2/15/05	destroyed			
MW-6	2/15/05	117.18	59.72	57.46	E
MW-7	2/15/05	99.71	43.16	56.55	E
MW-8	2/15/05	97.62	40.86	56.76	E
Deep Well					
MW-9	2/15/05	100.55	43.16	57.39	E

NOTES:

-Surveyed by Morrow Surveying to mean sea level 10/01.

TABLE 3
GROUNDWATER ANALYTICAL DATA
 Rotten Robbie
 7200 Healdsburg Ave , Sebastopol, California

Monitoring Well	Date Collected	TPH as Gasoline (ug/L)	TPH as Diesel (ug/L)	Aromatic Volatile Organics				MTBE (8260) (ug/L)	TAME (8260) (ug/L)	TBA (8260) (ug/L)
				Benzene (ug/L)	Toluene (ug/L)	Ethyl-benzene (ug/L)	Total Xylenes (ug/L)			
Shallow Wells										
MW-1	2/15/05	<50	<50	<0.50	0.58	<0.50	1.0	<0.50	<0.50	<5.0
MW-2	2/15/05	230	120	<0.50	4.1	0.91	1.8	9.8	<0.50	<5.0
MW-3	2/15/05	<50	<50	<0.50	<0.50	<0.50	<1.0	<0.50	<0.50	<5.0
MW-4	2/15/05	71,000	42,000	1,600	11,000	850	15,000	42	110	2,100
MW-5	2/15/05	destroyed								
MW-6	2/15/05	<50	<50	<0.50	<0.50	<0.50	<1.0	<0.50	<0.50	<5.0
MW-7	2/15/05	<50	<50	<0.50	0.55	<0.50	<1.0	<0.50	<0.50	<5.0
MW-8	2/15/05	<50	<50	<0.50	<0.50	<0.50	<1.0	<0.50	<0.50	<5.0
Deep Well										
MW-9	2/15/05	4,400	220	2,000	36	38	120	210	<2.5	<25

NOTES:

TPH - Total Petroleum Hydrocarbons

MTBE - Methyl Tertiary Butyl Ether

TBA - Tertiary Butyl Alcohol

TAME - Tertiary Amyl Methyl Ether

ug/L - micrograms per Liter

< -below laboratory detection limits

--- -Not Sampled

TABLE 4
HISTORICAL GROUNDWATER ELEVATION DATA
 Rotten Robbie
 7200 Healdsburg Avenue
 Sebastopol, California
 (All measurements are in feet)

Monitoring Well	Date	Reference Elevation (top of casing)	Depth to Groundwater (Feet)	Depth to FLH (Feet)	Groundwater Elevation (Feet)	FLH Thickness (Feet)	Groundwater Flow Direction
Shallow Wells							
MW-1	8/9/94	98.04	37.86		60.18		
	11/22/94		39.10		58.94		
	2/22/95		37.57		60.47		
	5/18/95		34.91		63.13		
	8/9/95		34.62		63.42		
	11/9/95		36.27		61.77		
	3/7/96		35.57		62.47		
	5/16/96		33.20		64.84		
	8/30/96		34.69		63.35		
	11/19/96		35.83		62.21		
	2/21/97		34.71		63.33		
	5/27/97		34.00		64.04		
	8/7/97		35.18		62.86		
	11/21/97		36.78		61.26		
	2/24/98		34.70		63.34		
	5/26/98		32.11		65.93		
	8/26/98		32.19		65.85		
	11/8/98		33.25		64.79		
	2/11/99		33.10		64.94		
	5/5/99		30.68		67.36		
	5/31/00		32.49		65.55		
	10/20/00		34.69		63.15		
	1/31/01		36.15		61.89		SE
	4/18/01		35.62		62.42		NE
	7/30/01		36.50		61.54		NE
	12/19/01	100.83	38.41		62.42		SW
	2/13/02		37.40		63.43		SE
	4/13/02		38.40		62.43		SE
	7/10/02		38.10		62.73		SE
	10/29/02		39.53		61.30		E
	1/15/03		40.03		60.80		SE
	4/9/03		39.05		61.78		E
	8/13/03		DRY		DRY		
	11/5/03		DRY		DRY		E
	2/18/04		DRY		DRY		SE
MW-2	6/16/04		DRY		DRY		S
	9/8/04		DRY		DRY		E
	12/21/04		DRY		DRY		E
	2/15/05		34.12		66.71		E
	8/9/94	99.74	39.28		60.46		
	11/22/94		40.53		59.21		
	2/22/95		38.95		60.79		
	5/18/95		36.30		63.44		
	8/9/95		36.06		63.68		
	11/9/95		37.73		62.01		
	3/7/96		36.97		62.77		
	5/16/96		35.35		64.39		
	8/30/96		36.15		63.59		
	11/19/96		37.31		62.43		
	2/21/97		36.16		63.58		
	5/27/97		35.48		64.26		
	8/7/97		36.65		63.09		
	11/21/97		38.33		61.41		
	2/24/98		36.14		63.60		
	5/26/98		33.58		66.16		
	8/26/98		33.69		66.05		
	11/8/98		34.60		65.14		
	2/11/99		34.58		65.16		
	5/6/99		32.07		67.67		
	5/31/00		33.84		65.90		
	10/20/00		36.27		63.47		
	1/31/01		37.57		62.17		
	4/18/01		36.95		62.79		NE
	7/30/01		38.14		61.60		NE
	12/19/01	102.36	39.75		62.60		SW
	2/13/02		38.70		63.66		SE
	4/13/02		38.72		63.63		SE
	7/10/02		39.44		62.91		SE
	10/29/02		41.18		61.17		E
	1/15/03		41.79		60.56		SE
	4/9/03		41.25		61.10		E
	8/13/03		41.41		60.94		E
	11/5/03		42.24		60.11		E
	2/19/04		42.14		60.21		E
	6/16/04		43.49		58.86		SE
	9/8/04		44.28		58.07		S
	12/21/04		45.02		57.33		E
	2/15/05		45.19		57.16		E

TABLE 4
HISTORICAL GROUNDWATER ELEVATION DATA
 Rotten Robbie
 7200 Healdsburg Avenue
 Sebastopol, California
 (All measurements are in feet)

Monitoring Well	Date	Reference Elevation (top of casing)	Depth to Groundwater (Feet)	Depth to FLH (Feet)	Groundwater Elevation (Feet)	FLH Thickness (Feet)	Groundwater Flow Direction
MW-3	8/9/94	103.21	18.78		84.43		
	11/22/94		19.99		83.22		
	2/22/95		17.60		86.61		
	5/18/95		13.39		89.62		
	8/9/95		12.51		90.70		
	11/9/95		14.50		88.71		
	3/7/96		13.88		89.33		
	5/16/96		12.10		91.11		
	8/30/96		13.28		89.93		
	11/19/96		14.66		88.55		
	2/21/97		13.65		89.66		
	5/27/97		11.93		91.28		
	8/7/97		13.32		89.89		
	11/21/97		15.48		87.73		
	2/24/98		10.14		93.07		
	5/26/98		8.05		95.16		
	8/26/98		9.56		93.65		
	11/8/98		11.33		91.88		
	2/11/99		10.71		92.50		
	5/5/99		8.30		94.91		
	5/31/00		9.21		94.00		
	10/20/00		12.22		90.99		
	1/31/01		12.91		90.30		SE
	4/18/01		11.70		91.51		SE
	7/30/01		14.03		89.18		NE
	12/19/01	103.21	16.05		87.16		SW
	2/13/02		13.30		89.91		SE
MW-4"	4/13/02		16.10		87.11		SE
	7/10/02		13.01		90.20		SE
	10/29/02		15.82		87.39		E
	1/15/03		14.89		88.32		SE
	4/9/03		14.52		88.69		E
	8/13/03		15.27		87.94		E
	11/5/03		15.63		87.58		E
	2/18/04		11.97		91.24		SE
	6/16/04		9.97		93.24		S
	9/8/04		11.02		92.19		E
	12/21/04		12.47		90.74		E
	2/15/05		11.41		91.80		E
	8/9/94	98.89	38.57	38.04	60.72	0.53	
	11/22/94		40.00	39.32	59.40	0.68	
	2/25/95		41.07	37.58	60.44	3.49	
	6/18/95		36.29	35.29	63.35	1.00	
	8/9/95		36.58	34.44	63.92	2.14	
	11/9/95		37.06	36.34	62.37	0.72	
	3/7/96		36.90	35.99	62.67	0.91	
	5/16/96		35.92	35.17	63.53	0.75	
	8/30/96		35.65	34.77	63.90	0.88	
	11/19/96		35.95	NA	63.04	sheen (<0.01)	
	2/21/97		35.48	NA	63.51	0.08	
	5/27/97		34.80	34.49	64.19	0.31	
	8/7/97		35.52	35.49	63.47	0.01	
	11/21/97		37.33	NA	61.66	0.00	
	2/24/98		35.72	NA	63.27	sheen (<0.01)	
	5/26/98		32.48	NA	66.51	sheen (<0.01)	
	8/26/98		32.48	NA	66.51	sheen (<0.01)	
	11/8/98		33.90	36.70	65.09	2.80	
	2/11/99		33.97	33.94	65.02	0.03	
	5/5/99		31.04	33.94	67.95	0.03	
	5/31/00		NM	NM	NM	0.07	
	10/20/00		NM	NM	NM	NM	
	1/31/01		38.03	37.33	60.96	0.70	SE
	4/18/01		NM	NM	NM	NM	NE
	7/30/01		NM	NM	NM	NM	NE
	12/19/01	101.76	NM	NM	NM	0.25	SW
	2/13/02		NM	NM	NM	0.25	SE
	4/13/02		NM	NM	NM	0.25	SE
	7/10/02		38.38	38.28	63.45	0.10	SE
	10/29/02		41.25	39.58	61.74	1.67	E
	1/15/03		41.99	40.43	60.92	1.56	SE
	4/9/03		39.50	0.00	62.26	0.00	E
	8/13/03		40.69	0.00	61.07	0.00	E
	11/5/03		41.21	41.09	60.64	0.12	E
	2/18/04		40.25	NM	61.51	0.00	SE
	6/16/04		40.41		61.35	0.00	S
	9/8/04		41.15	NM	60.61	0.00	E
	12/21/04		42.77	NM	58.99	0.00	E
	2/15/05		42.78	NM	58.98	0.00	E

TABLE 4

HISTORICAL GROUNDWATER ELEVATION DATA

Rotten Robbie
 7200 Healdsburg Avenue
 Sebastopol, California
 (All measurements are in feet)

Monitoring Well	Date	Reference Elevation (top of casing)	Depth to Groundwater (Feet)	Depth to FLH (Feet)	Groundwater Elevation (Feet)	FLH Thickness (Feet)	Groundwater Flow Direction
MW-5	8/9/94	NM	38.97		—		
	11/22/94		40.23		—		
	2/22/95		39.09		—		
	5/18/95		36.34		—		
	8/9/95		35.62		—		
	11/9/95		37.20		—		
	3/7/96		36.90		—		
	5/16/96		NM		—		
	8/30/96		35.76		—		
	11/19/96		36.71		—		
	2/21/97		NM		—		
	5/27/97		35.00		—		
	8/7/97		36.19		—		
	11/21/97		NM		—		
	2/24/98		NM		—		
	5/26/98		33.08		—		
	8/26/98		33.06		—		
	11/8/98		34.23		—		
	2/11/99		42.98		—		
	5/5/99		31.55		—		
	5/31/00		NM		—		
	10/20/00		NM		—		
	1/31/01		NM		—		SE
	4/18/01		NM		—		SE
	7/30/01		NM		—		NE
MW-6	10/29/02	102.50	40.25		62.25		E
	1/15/03		41.21		61.29		SE
	4/9/03		40.26		62.24		E
	8/13/03		40.98		61.52		E
	11/5/03		41.86		60.64		E
	2/18/04		destroyed				SE
MW-6	8/9/94	NM	53.93		—		
	11/22/94		55.21		—		
	2/2/95		53.85		—		
	5/18/95		50.99		—		
	8/9/95		50.78		—		
	11/9/95		52.38		—		
	3/7/96		51.78		—		
	5/16/96		NM		—		
	8/30/96		50.84		—		
	11/19/96		NM		—		
	2/21/97		NM		—		
	5/27/97		50.15		—		
	8/7/97		51.32		—		
	11/21/97		NM		—		
	2/24/98		NM		—		
	5/26/98		48.30		—		
	8/26/98		48.38		—		
	11/8/98		49.38		—		
	2/11/99		49.24		—		
	5/5/99		46.86		—		
	5/31/00		48.73		—		
	10/20/00		51.15		—		
	1/31/01		52.42		—		SE
	4/18/01		51.90		—		SE
	7/30/01		53.10		—		NE
MW-6	12/19/01	117.18	54.84		62.34		NE
	2/13/02		53.80		63.38		SW
	4/13/02		54.15		63.03		SE
	7/10/02		54.36		62.82		SE
	10/29/02		55.97		61.21		E
	1/15/03		56.67		60.54		SE
	4/9/03		55.57		61.61		SE
	8/13/03		56.39		60.79		E
	11/5/03		57.35		59.83		E
	2/18/04		57.56		59.62		SE
	6/16/04		57.01		60.17		E
	9/8/04		58.23		58.95		E
	12/21/04		59.52		57.66		SE
	2/15/05		49.72		67.46		SE

TABLE 4
HISTORICAL GROUNDWATER ELEVATION DATA
Rotten Robbie
7200 Healdsburg Avenue
Sebastopol, California
(All measurements are in feet)

Monitoring Well	Date	Reference Elevation (top of casing)	Depth to Groundwater (Feet)	Depth to FLH (Feet)	Groundwater Elevation (Feet)	FLH Thickness (Feet)	Groundwater Flow Direction
MW-7	8/9/94	97 17	37.32		59.85		
	11/22/94		38.62		58.55		
	2/22/95		NM		NM		
	5/18/95		34.58		62.59		
	8/9/95		34.20		62.97		
	11/9/95		35.85		61.32		
	3/7/96		35.29		61.88		
	5/16/96		33.54		63.63		
	8/30/96		34.23		62.94		
	11/19/96		35.37		61.80		
	2/21/97		34.44		62.73		
	5/27/97		33.58		63.59		
	8/7/97		34.76		62.41		
	11/21/97		36.44		60.73		
	2/24/98		34.82		62.35		
	5/26/98		31.80		65.37		
	8/26/98		31.76		65.41		
	11/8/98		32.82		64.35		
	2/11/99		32.57		64.60		
	5/5/99		30.28		66.89		
	5/31/00		32.13		65.04		
	10/20/00		34.59		62.58		
	1/31/01		35.79		61.38		SE
	4/18/01		NM		—		SE
	7/30/01		36.41		60.76		NE
	12/19/01	99 71	38.13		61.58		SW
	2/13/02		37.25		62.46		SE
	4/13/02		38.02		61.69		SE
	7/10/02		37.75		61.96		SE
	10/29/02		39.31		60.40		E
	1/15/03		40.07		59.64		SE
	4/9/03		39.03		60.68		E
	8/13/03		39.75		59.96		E
	11/5/03		40.65		59.06		E
	2/18/04		40.99		58.72		SE
	6/16/04		40.49		59.22		S
	9/8/04		41.65		58.06		E
	12/21/04		43.04		56.67		E
	2/15/05		43.16		56.55		E
MW-8	5/31/00	NM	29.88		—		SE
	10/20/00		32.38		—		SE
	1/31/01		33.59		—		SE
	4/18/01		32.46		—		NE
	7/30/01		34.18		—		NE
	12/19/01		36.84		60.78		SW
	2/13/02		36.00		61.62		SE
	4/13/02		36.53		61.09		SE
	7/10/02		35.58		62.04		SE
	10/29/02		37.10		60.52		E
	1/15/03		37.80		59.82		SE
	4/9/03		36.87		60.75		E
	8/13/03		37.64		59.98		E
	11/5/03		38.55		59.07		SE
	2/18/04		38.72		58.90		SE
Deep Well MW-9	6/16/04	NM	38.29		59.33		S
	9/8/04		39.40		58.22		E
	12/21/04		40.81		56.81		E
	2/15/05		40.86		56.76		E
	5/31/00	100 55	32.22		—		SE
	10/20/00		34.72		—		SE
	1/31/01		35.90		—		NE
	4/18/01		35.62		—		NE
	7/30/01		36.48		—		NE
	12/19/01		37.63		62.92		SW
	2/13/02		37.20		63.35		SE
	4/13/02		37.20		63.35		SE
	7/10/02		37.89		62.66		SE
	10/29/02		39.47		61.08		E
	1/15/03		40.12		60.43		SE
	4/9/03		39.07		61.48		E
	8/13/03		39.92		60.63		E
	11/5/03		40.82		59.73		SE
	2/18/04		40.86		59.69		SE
	6/16/04		40.69		59.86		S
	9/8/04		41.74		58.81		E
	12/21/04		43.11		57.44		E
	2/15/05		43.16		57.39		E

NOTES:

NA -Not applicable

NM -Not measured

-Surveyed by Morrow Surveying to mean sea level 10/01.

Historical Measurements are present in the Apex "Corrective Action Plan" dated October 14, 1994

* -Groundwater elevation was corrected for free product using TPHg density of 0.739

TABLE 5
HISTORICAL GROUNDWATER ANALYTICAL DATA
 Rotten Robbie
 7200 Healdsburg Avenue
 Sebastopol California

Monitoring Well	Date Collected	TPH as Gasoline (ug/L)	TPH as Diesel (ug/L)	Aromatic Volatile Organics				MTBE (8260) (ug/L)	TAME (8260) (ug/L)	TBA (8260) (ug/L)
				Benzene (ug/L)	Toluene (ug/L)	Ethyl-benzene (ug/L)	Total Xylenes (ug/L)			
Shallow Wells										
MW-1	8/9/94	17 000		5,300	50	64	29	—	—	—
	11/22/94	11,000		6,000	130	33	78	—	—	—
	2/22/95	16,000		7,600	65	93	15	—	—	—
	5/18/95	28 000		7,400	200	560	210	—	—	—
	8/9/95	21,000		12,000	360	690	290	—	—	—
	11/9/95	6,700		5,000	200	64	150	—	—	—
	3/7/96	10,000		2,900	139	<	59	—	—	—
	5/16/96	83,000		5,000	<300	<300	<300	—	—	—
	8/30/96	23,000		5,700	270	230	440	—	—	—
	11/19/96	14,000		6,500	240	250	480	—	—	—
	2/21/97	16 000		7,400	270	300	320	—	—	—
	5/27/97	26,000		7,500	290	150	370	—	—	—
	8/7/97	8,200		1,300	27	26	20	—	—	—
	11/21/97	7,700		4,700	61	88	100	—	—	—
	2/24/98	14,000		7,100	680	390	850	—	—	—
	5/26/98	12 000		3,000	260	300	430	15,000	—	—
	8/26/98	13 000		640	92	430	100	—	—	—
	11/8/98	37 000		2,800	860	580	1,900	—	—	—
	2/6/99	43 000		4,900	1,500	1,000	3,400	—	—	—
	5/6/99	27 000		4,400	2,900	1,400	5,300	—	—	—
	6/25/99							6,400	37	490
	6/1/00	12,000	4,500	3,700	790	1,300	2,400	37 000	220	<50
	10/20/00	39,000	<50	12,000	3,300	2,900	7,100	42,000	<10000	<100000
	2/1/01	54 000	2,300	15,000	4,200	3,200	8,000	48,000	130	<250
	4/18/01	44 000	2,000	14,000	2,200	3,400	6,600	41,000	<12,000	<1,200
	7/30/01	58 000	4,000	20,000	5,000	2,900	8,400	52,000	72	<500
	12/19/01	62,000	5,000	20,000	6,000	3,300	9,900	33,000	<1,200	<120
	2/13/02	16,000	1,800	9,800	1,300	2,200	3,500	23,000	<120	<1,200
	4/13/02	18,000	2,100	11,000	930	2,400	3,800	26,000	<120	<1,200
	7/10/02	37 000	18,000	15,000	1,900	3,200	6,700	26,000	<1 000	<10,000
	10/29/02	170	270	160	0.84	0.61	8.6	1,500	9.4	<50
	1/15/03	<50	540	<0.50	<0.50	<0.50	<1.0	34	<5.0	<50
	4/9/03	490	3,800	0.88	4.5	1.3	61	48	<0.50	<5.0
	8/13/03	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY
	11/5/03	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY
	2/18/04	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY
	6/16/04	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY
	9/8/04	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY
	12/21/04	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY
	2/15/05	<50	<50	<0.50	0.58	<0.50	1.0	<0.50	<0.50	<5.0
MW-2	8/9/94	21 000		4,400	4 000	24.0	1,200	—	—	—
	11/22/94	10,000		3,800	2,700	94.0	930	—	—	—
	2/22/95	8,000		2,800	410	81.0	510	—	—	—
	5/18/95	500		7.0	5.6	<	2.2	—	—	—
	8/9/95	1,700		180	150	25	80	—	—	—
	11/9/95	29 000		1,900	8,600	350	3,200	—	—	—
	3/7/96	21 000		3,900	2,300	91	750	—	—	—
	5/16/96	58 000		2,700	440	<300	970	—	—	—
	8/30/96	24 000		1,500	2,800	160	1,800	—	—	—
	11/19/96	21 000		2,200	4,700	510	3,300	—	—	—
	2/21/97	16,000		8,500	260	290	280	—	—	—
	5/27/97	14,000		800	650	<100	900	6,200	—	—
	8/7/97	3,600		440	660	140	170	1,600	—	—
	11/21/97	6,200		340	240	380	1,400	—	—	—
	2/24/98	4,900		27	7.6	72	30	20,000	—	—
	5/26/98	150,000		21,000	26,000	1,300	8,500	58,000	—	—
	8/26/98	30 000		<50	180.0	110	430	—	—	—
	11/8/98	73,000		530	5,500	670	5,100	97	—	—
	2/6/99	39,000		1,000	2,700	700	3,400	—	—	—
	5/6/99	3,700		240	56	280	930	—	—	—
	6/25/99							4,100	84	120
	6/1/00	20 000	4,100	63	4,500	1,100	6,500	650	<5.0	<50
	10/20/00	37,000	<50	180	1,000	1,900	9,400	240	<120	<2500
	2/1/01	48,000	1,300	200	12,000	2,500	9,600	320	<25	<250
	4/18/01	16,000	1,500	130	2,300	610	2,600	120	<5.0	<50
	7/30/01	13,000	2,700	42	1,700	440	3,500	<5.0	<5.0	<50
	12/19/01	33,000	3,500	150	7,300	2,100	8,600	170	<5.0	<50
	2/13/02	1,200	460	<0.50	52	30	99	28	<5.0	<50
	4/13/02	5,100	800	<5.0	980	380	1,400	75	<5.0	<50
	7/10/02	8,300	700	51	520	580	2,400	58	<5.0	<50
	10/29/02	11,000	610	48	820	790	3,700	73	<5.0	<50
	1/15/03	9,500	410	87	1,200	770	3,600	57	<5.0	<50
	4/9/03	1,000	<300	0.97	0.74	31	28	13	<0.50	17
	8/13/03	4,600	300	<10	29	760	700	37	<0.50	<5.0
	11/5/03	5,300	420	15	36	830	540	28	<5.0	<50
	2/18/04	70	<50	<0.50	<0.50	6.0	<1.0	12	<0.50	<5.0
	6/16/04	<50	120	<0.50	<0.50	<0.50	<1.0	2.0	<0.50	<5.0
	9/8/04	<50	<50	<0.50	<0.50	<0.50	<1.0	0.90	<0.50	<5.0
	12/21/04	<50	<50	<0.50	<0.50	<0.50	<1.0	1.0	<0.50	<5.0
	2/15/05	230	120	<0.50	4.1	0.91	1.8	9.8	<0.50	<5.0

TABLE 5
HISTORICAL GROUNDWATER ANALYTICAL DATA
 Rotten Robbie
 7200 Healdsburg Avenue
 Sebastopol California

Monitoring Well	Date Collected	TPH as Gasoline (ug/L)	TPH as Diesel (ug/L)	Aromatic Volatile Organics					MTBE (8260) (ug/L)	TAME (8260) (ug/L)	TBA (8260) (ug/L)
				Benzene (ug/L)	Toluene (ug/L)	Ethyl-benzene (ug/L)	Total Xylenes (ug/L)				
MW-3	8/9/94	<		<	<	<	<	<	---		
	11/22/94	<		<	<	<	<	<	---		
	2/22/95	<		<	<	<	<	<	---		
	5/18/95	<		<	<	<	<	<	---		
	8/9/95	<		<	<	<	<	<	---		
	11/9/95	<		<	<	<	<	<	---		
	3/7/96	52		2.30	2.90	<	1.8		---		
	5/16/96	<		<	<	<	<	<	---		
	8/30/96	<		<0.3	<0.3	<0.3	<0.3	<0.3	---		
	11/19/96	<		<	<	<	<	<	---		
	2/21/97	<50		<0.5	<0.5	<0.5	<0.5	<0.5	---		
	5/27/97	<50		<0.5	<0.5	<0.5	<0.5	<0.5	---		
	8/7/97	<50		4.70	<0.5	<0.5	<0.5	<0.5	---		
	11/21/97	<50		<0.50	0.50	0.50	<1.0		---		
	2/24/98	<50		<0.50	0.50	0.50	<1.0		---		
	5/26/98	<50		<0.50	<0.50	<0.50	<0.50	<0.50	---		
	8/26/98	<50		<0.50	<0.50	<0.50	<0.50	<0.50	---		
	11/8/98	110		<0.50	1.8	0.8	5.4		---		
	2/6/99	<50		<0.5	<0.5	<0.5	<0.5	<0.5	---		
	5/5/99	<50		<0.5	<0.5	<0.5	<1.0		---		
	6/25/99										
	5/31/00	<50	<50	1.7	1.4	1.1	3.6	<50	<50	<50	
	10/20/00	<50	<50	<0.50	<0.50	<0.50	<1.0	<50	<50	<50	
	2/1/01	<50	<50	<0.50	<0.50	<0.50	<1.0	<50	<50	<50	
	4/18/01	<50	<50	<0.50	<0.50	<0.50	<1.0	<50	<50	<50	
	7/30/01	<50	<50	<0.50	<0.50	<0.50	<1.0	16	<50	<50	
	12/19/01	<50	<50	<0.50	<0.50	<0.50	<1.0	<50	<50	<50	
	2/13/02	<50	<50	<0.50	<0.50	<0.50	<1.0	<50	<50	<50	
	4/13/02	<50	<50	<0.50	<0.50	<0.50	<1.0	<50	<50	<50	
	7/10/02	<50	<50	<0.50	<0.50	<0.50	<1.0	<50	<50	<50	
	10/29/02	<50	<50	<0.50	<0.50	<0.50	<1.0	<50	<50	<50	
	1/15/03	<50	<50	<0.50	<0.50	<0.50	<1.0	<50	<50	<50	
	4/9/03	<50	<50	<0.50	<0.50	<0.50	<0.50	<0.50	<50	<50	
	8/13/03	<50	<50	<0.50	<0.50	<0.50	<1.0	<50	<50	<50	
	11/5/03	<50	<50	<0.50	<0.50	<0.50	<1.0	<50	<50	<50	
	2/18/04	<50	<50	<0.50	<0.50	<0.50	<1.0	<50	<50	<50	
	6/16/04	<50	<50	<0.50	<0.50	<0.50	<1.0	<50	<50	<50	
	9/8/04	---	---	---	---	---	---	---	---	---	
	12/21/04	---	---	---	---	---	---	---	---	---	
	2/15/05	<50	<50	<0.50	<0.50	<0.50	<1.0	<50	<50	<50	
MW-4	8/9/94	FLH		FLH	FLH	FLH	FLH	FLH	FLH	FLH	
	11/22/94	FLH		FLH	FLH	FLH	FLH	FLH	FLH	FLH	
	2/22/95	FLH		FLH	FLH	FLH	FLH	FLH	FLH	FLH	
	5/18/95	FLH		FLH	FLH	FLH	FLH	FLH	FLH	FLH	
	8/9/95	FLH		FLH	FLH	FLH	FLH	FLH	FLH	FLH	
	11/9/95	FLH		FLH	FLH	FLH	FLH	FLH	FLH	FLH	
	3/7/96	FLH		FLH	FLH	FLH	FLH	FLH	FLH	FLH	
	5/16/96	FLH		FLH	FLH	FLH	FLH	FLH	FLH	FLH	
	8/30/96	FLH		FLH	FLH	FLH	FLH	FLH	FLH	FLH	
	11/19/96	FLH		FLH	FLH	FLH	FLH	FLH	FLH	FLH	
	2/21/97	FLH		FLH	FLH	FLH	FLH	FLH	FLH	FLH	
	5/27/97	FLH		FLH	FLH	FLH	FLH	FLH	FLH	FLH	
	8/7/97	FLH		FLH	FLH	FLH	FLH	FLH	FLH	FLH	
	11/21/97	170,000		37,000	56,000	2,700	16,000	NA			
	2/24/98	FLH		FLH	FLH	FLH	FLH	FLH	FLH	FLH	
	5/26/98	91,000		<500	9,600	3,100	17,000	8,000			
	8/26/98	FLH		FLH	FLH	FLH	FLH	FLH	FLH	FLH	
	11/8/98	FLH		FLH	FLH	FLH	FLH	FLH	FLH	FLH	
	2/6/99	FLH		FLH	FLH	FLH	FLH	FLH	FLH	FLH	
	5/6/99	170,000		33,000	67,000	8,700	56,000				
	6/25/99										
	5/31/00	FLH	FLH	FLH	FLH	FLH	FLH	2,700	<50	3,500	
	10/20/00	FLH	FLH	FLH	FLH	FLH	FLH	FLH	FLH	FLH	
	1/31/01	FLH	FLH	FLH	FLH	FLH	FLH	FLH	FLH	FLH	
	4/18/01	FLH	FLH	FLH	FLH	FLH	FLH	FLH	FLH	FLH	
	7/30/01	FLH	FLH	FLH	FLH	FLH	FLH	FLH	FLH	FLH	
	12/19/01	FLH	FLH	FLH	FLH	FLH	FLH	FLH	FLH	FLH	
	2/13/02	FLH	FLH	FLH	FLH	FLH	FLH	FLH	FLH	FLH	
	4/13/02	FLH	FLH	FLH	FLH	FLH	FLH	FLH	FLH	FLH	
	7/10/02	FLH	FLH	FLH	FLH	FLH	FLH	FLH	FLH	FLH	
	10/29/02	FLH	FLH	FLH	FLH	FLH	FLH	FLH	FLH	FLH	
	1/15/03	FLH	FLH	FLH	FLH	FLH	FLH	FLH	FLH	FLH	
	4/9/03	270,000	<220,000	16,000	44,000	5,200	29,000	220	<200	<2,000	
	8/13/03	920,000	38,000	13,000	34,000	20,000	51,000	310	<100	<1,000	
	11/5/03	FLH	FLH	FLH	FLH	FLH	FLH	FLH	FLH	FLH	
	2/18/04	240,000	310,000	15,000	36,000	3,300	30,000	180	<50	<50	
	6/16/04	83,000	6,400	3,800	22,000	2,400	15,000	190	130	1,800	
	9/8/04	97,000	870,000	3,300	17,000	1,800	20,000	85	120	1,300	
	12/21/04	110,000	58,000	3,800	19,000	2,000	27,000	140	140	2,400	
	2/15/05	71,000	42,000	1,600	11,000	850	15,000	42	110	2,100	

TABLE 5
HISTORICAL GROUNDWATER ANALYTICAL DATA
 Rotten Robbie
 7200 Healdsburg Avenue
 Sebastopol California

Monitoring Well	Date Collected	TPH as Gasoline (ug/L)	TPH as Diesel (ug/L)	Aromatic Volatile Organics				MTBE (8260) (ug/L)	TAME (8260) (ug/L)	TBA (8260) (ug/L)
				Benzene (ug/L)	Toluene (ug/L)	Ethyl-benzene (ug/L)	Total Xylenes (ug/L)			
MW-5	8/9/94	---	---	---	---	---	---	---	---	---
	11/22/94	---	---	---	---	---	---	---	---	---
	2/22/95	---	---	---	---	---	---	---	---	---
	5/18/95	---	---	---	---	---	---	---	---	---
	8/9/95	---	---	---	---	---	---	---	---	---
	11/9/95	---	---	---	---	---	---	---	---	---
	3/7/96	---	---	---	---	---	---	---	---	---
	5/16/96	---	---	---	---	---	---	---	---	---
	8/30/96	---	---	---	---	---	---	---	---	---
	11/19/96	---	---	---	---	---	---	---	---	---
	2/21/97	---	---	---	---	---	---	---	---	---
	5/27/97	---	---	---	---	---	---	---	---	---
	8/7/97	---	---	---	---	---	---	---	---	---
	11/21/97	---	---	---	---	---	---	---	---	---
	2/24/98	---	---	---	---	---	---	---	---	---
	5/26/98	---	---	---	---	---	---	---	---	---
	8/26/98	---	---	---	---	---	---	---	---	---
	11/8/98	---	---	---	---	---	---	---	---	---
	2/6/99	---	---	---	---	---	---	---	---	---
	5/5/99	<50	---	<0.5	<0.5	<0.5	<1.0	---	---	---
	6/25/99	---	---	---	---	---	---	<5.0	<5.0	<50
	5/31/00	---	---	---	---	---	---	---	---	---
	10/20/00	---	---	---	---	---	---	---	---	---
	1/31/01	---	---	---	---	---	---	---	---	---
	4/18/01	---	---	---	---	---	---	---	---	---
	7/30/01	---	---	---	---	---	---	---	---	---
	10/29/02	<50	<50	<0.50	<0.50	<0.50	<1.0	---	<5.0	<5.0
	1/15/03	<50	<50	<0.50	<0.50	<0.50	<1.0	---	<5.0	<50
	4/9/03	<50	52	<0.50	<0.50	<0.50	<0.50	---	<0.50	<0.50
	8/13/03	<50	<50	<0.50	<0.50	<0.50	<1.0	---	<0.50	<0.50
	11/5/03	<50	<50	<0.50	<0.50	<0.50	<1.0	---	<0.50	<0.50
	2/18/04	destroyed		---	---	---	---	---	---	---
MW-6	8/9/94	---	---	---	---	---	---	---	---	---
	11/22/94	---	---	---	---	---	---	---	---	---
	2/22/95	---	---	---	---	---	---	---	---	---
	5/18/95	---	---	---	---	---	---	---	---	---
	8/9/95	---	---	---	---	---	---	---	---	---
	11/9/95	---	---	---	---	---	---	---	---	---
	3/7/96	---	---	---	---	---	---	---	---	---
	5/16/96	---	---	---	---	---	---	---	---	---
	8/30/96	---	---	---	---	---	---	---	---	---
	11/19/96	---	---	---	---	---	---	---	---	---
	2/21/97	---	---	---	---	---	---	---	---	---
	5/27/97	---	---	---	---	---	---	---	---	---
	8/7/97	---	---	---	---	---	---	---	---	---
	11/21/97	---	---	---	---	---	---	---	---	---
	2/24/98	---	---	---	---	---	---	---	---	---
	5/26/98	---	---	---	---	---	---	---	---	---
	8/26/98	---	---	---	---	---	---	---	---	---
	11/8/98	---	---	---	---	---	---	---	---	---
	2/6/99	---	---	---	---	---	---	---	---	---
	5/5/99	<50	---	<0.5	<0.5	<0.5	<1.0	---	---	---
	6/25/99	---	---	---	---	---	---	---	---	---
	5/31/00	<50	<50	8.3	4.5	2.4	8.7	7.2	<5.0	<50
	10/20/00	<50	<50	<0.50	<0.50	<0.50	<1.0	---	<5.0	<50
	2/1/01	<50	<50	<0.50	<0.50	<0.50	<1.0	---	<5.0	<50
	4/18/01	<50	<50	<0.50	<0.50	<0.50	<1.0	---	<5.0	<50
	7/30/01	<50	<50	<0.50	<0.50	<0.50	<1.0	---	<5.0	<50
	12/19/01	<50	<50	<0.50	<0.50	<0.50	<1.0	---	<5.0	<50
	2/13/02	CAR PARKED OVER WELL						---	---	---
	4/13/02	<50	<50	<0.50	<0.50	<0.50	<1.0	---	<5.0	<50
	7/10/02	<50	<50	<0.50	<0.50	<0.50	<1.0	7.8	<5.0	<50
	10/29/02	<50	<50	<0.50	<0.50	<0.50	<1.0	---	<5.0	<50
	1/15/03	<50	<50	<0.50	<0.50	<0.50	<1.0	---	<5.0	<50
	4/9/03	<50	<50	<0.50	<0.50	<0.50	<0.50	0.67	<0.50	<50
	8/13/03	<50	<50	<0.50	<0.50	<0.50	<1.0	---	<0.50	<50
	11/5/03	<50	<50	<0.50	<0.50	<0.50	<1.0	---	<0.50	<50
	2/18/04	<50	<50	<0.50	<0.50	<0.50	<1.0	---	<0.50	<50
	6/16/04	<50	<50	<0.50	<0.50	<0.50	<1.0	---	<0.50	<50
	9/8/04	---	---	---	---	---	---	---	---	---
	12/21/04	---	---	---	---	---	---	---	---	---
	2/15/05	<50	<50	<0.50	<0.50	<0.50	<1.0	---	<0.50	<50

TABLE 5
HISTORICAL GROUNDWATER ANALYTICAL DATA
 Rotten Robbie
 7200 Healdsburg Avenue
 Sebastopol, California

Monitoring Well	Date Collected	TPH as Gasoline (ug/L)	TPH as Diesel (ug/L)	Aromatic Volatile Organics					MTBE (8260) (ug/L)	TAME (8260) (ug/L)	TBA (8260) (ug/L)
				Benzene (ug/L)	Toluene (ug/L)	Ethyl-benzene (ug/L)	Total Xylenes (ug/L)				
MW-7	8/9/94	<		<	<	<	<	<	---		
	11/22/94	<		<	<	<	<	<	---		
	2/22/95	--		--	--	--	--	--	---		
	5/18/95	<		<	<	<	<	<	---		
	8/9/95	<		<	<	<	<	<	---		
	11/9/95	<		<	<	<	<	<	---		
	3/7/96	<		0.70	1.00	<	<	0.70	---		
	5/16/96	<		<	<	<	<	<	---		
	8/30/96	<		<0.3	<0.3	<0.3	<0.3	<0.3	---		
	11/19/96	<		<	<	<	<	0.58	---		
	2/21/97	<50		<0.5	<0.5	<0.5	<0.5	0.62	---		
	5/27/97	<50		<0.5	<0.5	<0.5	<0.5	<0.5	---		
	8/7/97	<50		<0.5	<0.5	<0.5	<0.5	<0.5	---		
	11/21/97	<50		<0.50	<0.50	<0.50	<1.0	---			
	2/24/98	<50		<0.50	<0.50	<0.50	<1.0	---			
	5/26/98	<50		<0.50	<0.50	<0.50	<0.50	---			
	8/26/98	<50		<0.50	<0.50	<0.50	<0.50	---			
	11/8/98	140		<0.50	3.4	1.3	9.0	---			
	2/6/99	<50		<0.5	<0.5	0.68	0.66	---			
	5/5/99	<50		<0.5	<0.5	<0.5	<1.0	---			
	6/25/99	---		---	---	---	---	---			
	5/31/00	<50	<50	0.97	<0.50	<0.50	1.20	<5.0	<5.0	<5.0	<5.0
	10/20/00	<50	<50	<0.50	<0.50	<0.50	<1.0	<5.0	<5.0	<5.0	<5.0
	1/31/01	<50	<50	<0.50	<0.50	<0.50	<1.0	<5.0	<5.0	<5.0	<5.0
	4/19/01	--	--	--	--	--	--	---	--	--	--
	7/30/01	<50	<50	<0.50	<0.50	<0.50	<1.0	<5.0	<5.0	<5.0	<5.0
	12/19/01	<50	<50	<0.50	<0.50	<0.50	<1.0	<5.0	<5.0	<5.0	<5.0
	2/13/02	<50	<50	<0.50	<0.50	<0.50	<1.0	<5.0	<5.0	<5.0	<5.0
	4/13/02	<50	<50	<0.50	<0.50	<0.50	<1.0	<5.0	<5.0	<5.0	<5.0
	7/10/02	<50	<50	<0.50	<0.50	<0.50	<1.0	7.8	<5.0	<5.0	<5.0
	10/29/02	<50	<50	<0.50	<0.50	<0.50	<1.0	<5.0	<5.0	<5.0	<5.0
	1/15/03	<50	<50	<0.50	<0.50	<0.50	<1.0	<5.0	<5.0	<5.0	<5.0
	4/9/03	<50	<50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50
	8/13/03	<50	<50	<0.50	<0.50	<0.50	<1.0	<0.50	<0.50	<0.50	<0.50
	11/5/03	<50	<50	<0.50	<0.50	<0.50	<1.0	<0.50	<0.50	<0.50	<0.50
	2/18/04	<50	<50	<0.50	<0.50	<0.50	<1.0	<0.50	<0.50	<0.50	<0.50
	6/16/04	<50	<50	<0.50	<0.50	<0.50	<1.0	<0.50	<0.50	<0.50	<0.50
	9/8/04	--	--	--	--	--	--	---	--	--	--
	12/21/04	--	--	--	--	--	--	---	--	--	--
	2/15/05	<50	<50	<0.50	0.55	<0.50	<1.0	<0.50	<0.50	<0.50	<0.50
MW-8	5/31/00	<50	<50	0.85	<0.50	<0.50	<1.0	<5.0	<5.0	<5.0	<5.0
	10/20/00	<50	<50	<0.50	<0.50	<0.50	<1.0	<5.0	<5.0	<5.0	<5.0
	1/31/01	<50	<50	<0.50	<0.50	<0.50	<1.0	<5.0	<5.0	<5.0	<5.0
	4/18/01	<50	<50	<0.50	<0.50	<0.50	<1.0	<5.0	<5.0	<5.0	<5.0
	7/30/01	<50	<50	<0.50	<0.50	<0.50	<1.0	9.0	<5.0	<5.0	<5.0
	12/19/01	<50	<50	<0.50	<0.50	<0.50	<1.0	<5.0	<5.0	<5.0	<5.0
	2/13/02	<50	<50	<0.50	<0.50	<0.50	<1.0	<5.0	<5.0	<5.0	<5.0
	4/13/02	<50	<50	<0.50	<0.50	<0.50	<1.0	<5.0	<5.0	<5.0	<5.0
	7/10/02	<50	<50	<0.50	<0.50	<0.50	<1.0	8.1	<5.0	<5.0	<5.0
	10/29/02	<50	<50	<0.50	<0.50	<0.50	<1.0	<5.0	<5.0	<5.0	<5.0
	1/15/03	<50	<50	<0.50	<0.50	<0.50	<1.0	<5.0	<5.0	<5.0	<5.0
	4/9/03	<50	<50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50
	8/13/03	<50	<50	<0.50	<0.50	<0.50	<1.0	<0.50	<0.50	<0.50	<0.50
	11/5/03	<50	<50	<0.50	<0.50	<0.50	<1.0	<0.50	<0.50	<0.50	<0.50
	2/18/04	<50	<50	<0.50	<0.50	<0.50	<1.0	<0.50	<0.50	<0.50	<0.50
	6/16/04	<50	<50	<0.50	<0.50	<0.50	<1.0	<0.50	<0.50	<0.50	<0.50
	9/8/04	--	--	--	--	--	--	---	--	--	--
	12/21/04	--	--	--	--	--	--	---	--	--	--
	2/15/05	<50	<50	<0.50	<0.50	<0.50	<1.0	<0.50	<0.50	<0.50	<0.50

TABLE 5
HISTORICAL GROUNDWATER ANALYTICAL DATA
 Rotten Robbie
 7200 Healdsburg Avenue
 Sebastopol California

Monitoring Well	Date Collected	TPH as Gasoline (ug/L)	TPH as Diesel (ug/L)	Aromatic Volatile Organics				MTBE (8260) (ug/L)	TAME (8260) (ug/L)	TBA (8260) (ug/L)
				Benzene (ug/L)	Toluene (ug/L)	Ethyl-benzene (ug/L)	Total Xylenes (ug/L)			
Deep Well MW-9	6/1/00	6 100	330	8,500	80	15	70	420	<50	<500
	10/20/00	3 700	1.0	3,200	23	3.4	14	150	<50	1,200
	2/1/01	4 200	230	3,200	27	3.7	17	290	<50	2,200
	4/18/01	3,400	340	2,400	13	1.8	97	270	<50	1,300
	7/30/01	1,300	870	970	2.2	0.63	2.1	<5.0	<5.0	<50
	12/19/01	920	330	800	3.3	3.4	<1.0	12	<5.0	1,700
	2/13/02	470	62	1,100	0.79	3.6	<1.0	20	<5.0	1,200
	4/13/02	480	1,400	1,300	<0.50	3.8	<1.0	28	<5.0	1,900
	7/10/02	69	<50	<0.50	<0.50	<0.50	<1.0	22	<5.0	900
	10/29/02	650	<50	330	<0.50	1.2	2.2	64	<5.0	1,600
	1/15/03	110	<50	1.7	<0.50	<0.50	<1.0	52	<5.0	1,000
	4/9/03	5,500	<80	64	3.8	2.2	14	63	<0.50	610
	8/13/03	700	<50	290	<0.50	<0.50	2.0	71	<0.50	610
	11/5/03	1,100	290	650	1.6	0.95	27	120	<0.50	1,100
	2/18/04	850	240	500	2.4	0.55	1.6	130	<0.50	970
	6/16/04	1 100	1300	5.3	1.4	2.4	1.6	240	82	1,400
	9/8/04	3,100	270	1,700	7.6	2.2	4.4	390	110	1,600
	12/21/04	690	290	2,100	5.9	2.1	2.7	370	70	1,200
	2/15/05	4,400	220	2,000	36	38	120	210	<2.5	<25
AS-2	5/16/00	81,000	2,000	5,700	37,000	3,900	23,000	26,000	80	<50
AS-3	5/16/00	<50	<50	19	18	3.4	14	17	<5.0	<50

NOTES:

TPH - Total Petroleum Hydrocarbons
 MTBE - Methyl Tertiary Butyl Ether

TBA - Tertiary Butyl Alcohol

TAME - Tertiary Amyl Methyl Ether

--- -Not analyzed

ug/L - micrograms per Liter

< -below laboratory detection limits

FLH - Floating Liquid Hydrocarbons, not sampled

Historical Groundwater Analytical is present in the Apex Corrective Action Plan dated October 14 1994

Table 6
Soil Vapor Extraction Rate Calculations
 Rotten Robbie
 7200 Healdsburg Avenue
 Sebastopol, California

Date	Meter	Vapor Flow Rate	Thermal Oxidizer Influent Sample Results (ppmv)			Extraction Rates (lb/day)			Cumulative Extraction (lb)		
			(Hours)	(scfm)	TPHg	Benzene	MTBE	TPHg	Benzene	MTBE	TPHg
09/17/02	3.0										
10/09/02	170.4	167.4	87	500	4.9	0.1	15	0.1	0.00	102	0.9
11/06/02	633.8	463.4	83	1,200	12	0.4	34	0.29	0.01	568	5
12/11/02	1,388.4	754.6	92	920	38	6.0	29	1.02	0.18	1,544	26
12/31/02	1,476.5	881.1	92	920	38	6.0	29	1.02	0.18	1,649	29
01/26/03	1,938.2	461.7	81	1,100	17	<0.4	30	0.40	0.01	2,212	43
02/25/03	2,806.7	668.5	78	600	5.1	<0.22	16	0.12	0.006	2,850	50
03/14/03	3,014.5	407.8	78	540	6.0	<0.27	14	0.14	0.007	3,105	52
03/31/03	3,435.7	829.0	78	540	6.0	<0.27	14	0.14	0.007	3,595	57
04/09/03	3,637.5	201.8	78	420	5.0	<0.28	11	0.11	0.007	3,701	58
05/07/03	4,308.7	671.2	78	380	4.9	<0.28	10	0.11	0.007	3,995	61
06/03/03	4,952.7	644.0	63	530	5.6	<0.28	11	0.10	0.006	4,278	64
07/08/03	5,781.8	829.1	63	590	6.0	<0.28	13	0.11	0.006	4,688	68
08/20/03	6,575.5	793.7	72	720	6.8	<0.28	17	0.14	0.007	5,184	72
09/03/03	6,909.0	333.5	75	510	4.0	<0.28	13	0.09	0.007	5,395	74
10/09/03	7,773.0	884.0	63	120	1.0	<0.10	3	0.02	0.006	5,673	76
11/06/03	8,421.2	648.2	79	560	11.0	<0.28	15	0.25	0.007	5,908	79
12/11/03	9,115.6	634.4	75	200	1.4	<0.13	5	0.03	0.007	6,197	83
01/06/04	9,438.1	322.5	83	300	3.3	<0.13	8	0.08	0.008	6,288	84
02/17/04	10,045.8	607.7	93	2,500	36.0	<1.0	78	0.98	0.009	7,386	98
03/16/04	10,377.7	331.9	82	1,300	14.0	<1.0	36	0.34	0.008	8,176	107
04/14/04	11,026.7	649.0	74	3,900	64.0	<0.40	97	1.39	0.010	9,979	130
05/04/04	11,270.9	244.2	69	2,200	31.0	<2.0	51	0.62	0.045	10,734	140
06/03/04	11,783.1	512.2	75	3,600	41.0	<2.0	91	0.90	0.050	12,254	156
07/08/04	12,462.8	679.7	60	1,500	22.0	<1.3	30	0.39	0.026	13,979	175
08/05/04	13,136.0	673.2	53	1,500	11.0	<0.67	27	0.17	0.012	14,784	183
09/09/04	13,859.9	723.9	80	2,900	38.0	<1.0	78	0.89	0.026	16,368	199
10/07/04	14,532.7	672.8	61	1,700	12.0	<0.25	35	0.21	0.005	17,949	214
11/11/04	15,375.9	843.2	59	1,400	11.0	<0.67	28	0.19	0.013	19,051	221
12/07/04	15,989.9	614.0	75	1,800	16.0	<0.25	46	0.36	0.006	19,980	228
01/05/05	16,304.5	314.6	65	2,900	30.0	<0.70	64	0.57	0.015	20,707	234
02/01/05	16,836.1	581.6	59	1,500	11.0	<0.30	30	0.19	0.006	21,842	243
03/03/05	17,148.0	531.9	54	1,500	8.8	<0.30	27	0.14	0.005	22,475	247
											13.5

Note 1: Source Test conducted on 9/17/02. Quarterly calculations do not include the source test.

Note 2: Sample results from the thermal oxidizer influent used in place of the vapor extraction well manifold.

Note 3: *^a indicates analytical method detection limit; method detection limits are used as stack concentrations to estimate emission rates and DEs.

Note 4: Analytical results from 03/14/03 are used to extrapolate cumulative totals through 03/31/03.
 $MW_{TPHa} = 90$
 $MW_{Benzene} = 88.15$
 $MW_{MTBE} = 78.11$

Sample Calculations

lb/day = pounds per day

ppmv = parts per million by volume = $ft^3 / 1 \times 10^6 ft^3$

scfm = standard cubic feet per minute

Extraction Rate = flow rate(ft^3/min) * concentration ($ft^3 / 1 \times 10^6 ft^3$) * MW (lb/lb-mole)284.5 (lb/lb-mole) * 1440 min/day

ft^3 = cubic feet

Table 7
Thermal Oxidizer Destruction Efficiency and Emission Rate Calculations
Rotten Robbie
7200 Healdsburg Avenue
Sebastopol, California

Date	Meter	Stack Flow Rate (scfm)	Stack Sample Results (ppmv)			Emission Rates (lb/day)			Destruction Efficiency (%)		
			TPHg	Benzene	MTBE	TPHg	Benzene	MTBE	TPHg	Benzene	MTBE
9/17/02	3.0	<5.0	0.35	<0.05	0.15	0.0013	0.003	99.0	99.0	99.0	28.6
10/9/02	170.4	87	<5.0	<0.05	0.14	0.0012	0.003	99.6	99.6	99.6	77.3
11/6/02	633.8	83	<5.0	<0.05	0.16	0.0013	0.003	99.5	99.5	99.5	98.3
12/11/02	1,388.4	92	0.8	<0.001	0.16	0.0013	0.003	99.5	99.5	99.5	98.3
1/28/03	1,938.2	86	<5.0	<0.05	0.14	0.0013	0.003	99.5	99.5	99.5	73.5
2/25/03	2,606.7	83	<5.0	<0.05	0.14	0.0012	0.003	99.1	99.1	99.1	51.6
3/14/03	3,014.5	83	<5.0	<0.05	0.14	0.0012	0.003	99.0	99.1	99.1	60.6
4/9/03	3,637.5	83	<5.0	<0.05	0.14	0.0012	0.003	99.0	99.1	99.1	60.4
5/7/03	4,308.7	83	<5.0	<0.05	0.14	0.0012	0.003	98.7	98.9	98.9	62.0
6/3/03	4,952.7	68	<5.0	<0.05	0.10	0.0010	0.002	98.9	99.1	99.1	68.9
7/8/03	5,781.8	68	<5.0	<0.05	0.10	0.0010	0.002	99.0	99.0	99.0	61.1
8/20/03	6,575.5	77	<5.0	<0.05	0.10	0.0011	0.003	99.0	99.0	99.0	56.3
9/3/03	6,909.0	80	<5.0	<0.05	0.13	0.0012	0.003	98.2	99.2	99.2	60.3
10/9/03	7,773.0	68	<5.0	<0.05	0.11	0.0010	0.002	99.1	98.9	98.9	67.6
11/6/03	8,421.2	84	<5.0	<0.05	0.14	0.0012	0.003	94.4	93.3	93.3	52.4
12/11/03	9,115.6	80	<5.0	<0.05	0.13	0.0012	0.003	99.1	99.5	99.5	63.8
1/6/04	9,438.1	88	<5.0	<0.05	0.10	0.0013	0.003	97.1	95.8	95.8	58.1
2/17/04	10,045.8	98	<5.0	<0.05	0.10	0.0014	0.003	98.0	98.2	98.2	57.8
3/16/04	10,377.7	83	<5.0	<0.05	0.14	0.0012	0.003	99.8	99.9	99.9	68.1
4/14/04	11,026.7	79	<5.0	<0.05	0.10	0.0012	0.003	99.6	99.7	99.7	65.6
5/4/04	11,270.9	73	<5.0	<0.05	0.10	0.0011	0.002	99.9	99.9	99.9	75.3
6/3/04	11,783.1	80	<5.0	<0.05	0.10	0.0012	0.003	99.7	99.8	99.8	94.2
7/8/04	12,462.8	65	<5.0	<0.05	0.11	0.0009	0.002	99.9	99.9	99.9	95.7
8/5/04	13,136.0	59	<5.0	<0.05	0.10	0.0009	0.002	99.7	99.8	99.8	92.5
9/9/04	13,859.9	85	<5.0	<0.05	0.10	0.0012	0.003	99.5	99.3	99.3	76.2
10/7/04	14,532.7	66	<5.0	<0.05	0.10	0.0010	0.002	99.9	99.9	99.9	91.7
11/11/04	15,375.9	64	<5.0	<0.05	0.10	0.0009	0.002	99.7	99.6	99.6	57.7
12/7/04	15,989.9	80	<5.0	<0.05	0.10	0.0012	0.003	99.5	99.4	99.4	79.7
1/5/05	16,304.5	71	<5.0	<0.05	0.12	0.0010	0.002	99.7	99.7	99.7	62.2
2/1/05	16,886.1	64	<5.0	<0.05	0.11	0.0009	0.002	99.8	99.8	99.8	86.0
3/3/05	17,418.0	68	<5.0	<0.05	0.10	0.0010	0.002	99.6	99.5	99.5	61.6

Note 1: * indicates analytical method detection limit; method detection limits are used as stack concentrations to estimate emission rates and DEs.

$$\text{MW}_{\text{TPHg}} = 90 \quad \text{MW}_{\text{Benzene}} = 78.11 \quad \text{MW}_{\text{MTBE}} = 88.15$$

Sample Calculations

lb/day = pounds per day

NS = not sampled

ppmv = parts per million by volume = $\text{ft}^3 / 1 \times 10^6 \text{ ft}^3$

scfm = standard cubic feet per minute

Emission rate = flow rate(ft^3/min) * concentration ($\text{ft}^3 / 1 \times 10^6 \text{ ft}^3$) * MW (lb/mole)/384.5 ($\text{ft}^3/\text{lb}\cdot\text{mole}$) * 1440 min/day

Destruction Efficiency = [(Extraction rate - Emission rate)/Extraction rate] * 100%

ft^3 = cubic feet

APPENDIX A

APEX STANDARD OPERATING PROCEDURES

APEX ENVIROTECH, INC.
STANDARD OPERATING PROCEDURES
Quarterly Monitoring Reports

SOP - 4
SAMPLE IDENTIFICATION AND CHAIN-
OF-CUSTODY PROCEDURES

Sample identification and chain-of-custody procedures ensure sample integrity as well as document sample possession from the time of collection to ultimate disposal. Each sample container submitted for analysis is labeled to identify the job number, date, time of sample collection, a sample number unique to the sample, any in-field measurements made, sampling methodology, name(s) of on-site personnel, and any other pertinent field observations also recorded on the field excavation or boring log.

Chain-of-custody forms are used to record possession of the sample from time of collection to arrival at the laboratory. During shipment, the person with custody of the samples will relinquish them to the next person by signing the chain-of-custody form(s) and noting the date and time. The sample-control officer at the laboratory will verify sample integrity, correct preservation, confirm collection in the proper container(s), and ensure adequate volume for analysis.

If these conditions are met, the samples will be assigned unique laboratory log numbers for identification throughout analysis and reporting. The log numbers will be recorded on the chain-of-custody forms and in the legally-required log book maintained in the laboratory. The sample description, date received, client's name, and any other relevant information will also be recorded.

SOP - 5
LABORATORY ANALYTICAL QUALITY
ASSURANCE AND CONTROL

In addition to routine instrument calibration, replicates, spikes, blanks, spiked blanks, and certified reference materials are routinely analyzed at method-specific frequencies to monitor precision and bias. Additional components of the laboratory Quality Assurance/Quality Control program include:

1. Participation in state and federal laboratory accreditation/certification programs;
2. Participation in both U.S. EPA Performance Evaluation studies (WS and WP studies) and inter-laboratory performance evaluation programs;
3. Standard operating procedures describing routine and periodic instrument maintenance;
4. "Out-of-Control" /Corrective Action documentation procedures; and,
5. Multi-level review of raw data and client reports.

SOP - 7
GROUNDWATER PURGING AND
SAMPLING

Prior to water sampling, each well is purged by evacuating a minimum of three wetted well-casing volumes of groundwater. When required, purging will continue until either the discharge water temperature, conductivity, or pH stabilize, a maximum of ten wetted-casing volumes of groundwater have been recovered, or the well is bailed dry.

When practical, the groundwater sample should be collected when the water level in the well recovers to at least 80 percent of its static level.

The sampling equipment consists of either a "Teflon" bailer, PVC bailer, or stainless steel bladder pump with a "Teflon" bladder. If the sampling system is dedicated to the well, then the bailer is usually "Teflon," but the bladder pump is PVC with a polypropylene bladder. In general and depending on the intended laboratory analysis, 40-milliliter glass, volatile organic analysis (VOA) vials with "Teflon" septa, are used as sample containers.

SOP - 12
MEASURING LIQUID LEVELS USING
WATER LEVEL METER OR INTERFACE
PROBE

Field equipment used for liquid-level gauging typically includes the measuring instrument (water-level meter or interface probe) and product bailer(s). The field kit also includes cleaning supplies (buckets, solution, spray bottles, and deionized water) to be used in cleaning the equipment between wells.

Prior to measurement, the instrument tip is lowered into the well until it touches bottom. Using the previously established top-of-casing or top-of-box (i.e., wellhead vault) point, the probe cord (or halyard) is marked and a measuring tape (graduated in hundredths of a foot) is used to determine the distance between the probe end and the marking on the cord. This measurement is then recorded on the liquid-level data sheet as the "Measured Total Depth" of the well.

When necessary in using the interface probe to measure liquid levels, the probe is first electrically grounded to either the metal stove pipe or another metal object nearby. When no ground is available, reproducible measurements can be obtained by clipping the ground lead to the handle of the interface probe case.

The probe tip is then lowered into the well and submerged in the groundwater. An oscillating (beeping) tone indicates the probe is in water. The probe is slowly raised until either the oscillating tone ceases or becomes a steady tone. In either case, this is the depth-to-water (DTW) indication and the DTW measurement is made accordingly. The steady tone indicates floating liquid hydrocarbons (FLH). In this case, the probe is slowly raised until the steady tone ceases. This is the depth-to-product (DTP) indication and the DTP measurement is made accordingly.

The process of lowering and raising the probe must be repeated several times to ensure accurate measurements. The DTW and DTP measurements are recorded on the liquid-level data sheet. When FLH are indicated by the probe's response, a product bailer is lowered partially through the FLH-water interface to confirm the FLH on the water surface and as further indication of the FLH thickness, particularly in cases where the FLH layer is quite thin. This measurement is recorded on the data sheet as "FLH thickness."

In order to avoid cross-contamination of wells during the liquid-level measurement process, wells are measured in the order of "clean" to "dirty" (where such information is available). In addition, all measurement equipment is cleaned with solution and thoroughly rinsed with deionized water before use, between measurements in respective wells, and at the completion of the day's use.

APPENDIX B

FIELD DATA SHEETS



ENVIROTECH, INC.

Groundwater Level Data Sheet

Project ERA02-005
Location Sebastopol, CA
Date 2/15/05
Recorded By RCM

Well Volume Calculation:

(2" x 0.16) (4" x 0.65)



Monitoring Data

Project: Former Dave's Pit Stop
 Project Number: ERA02.005
 Date: 2/15/05
 Recorded By: RCM

WELL	TIME	TEMP (deg)	pH	COND. ($\mu\text{S}/\text{cm}$)	DISSOLVED OXYGEN	TOTAL VOLUME REMOVED	COMMENTS/OBSERVATIONS
MW-6	1145	16.6	5.9	171		0.75	
MW-3	1201	16.4	5.8	66	4		
	1213	16.4	5.6	225		8.25	
	1226	16.4	5.7	215		12.50	
MW-8	1236	17.7	5.8	381		0.25	
	1258	17.6	5.6	241		0.50	
MW-7							

1. 80 sec Well dry @ 0.75 gal purged
 2. 25 sec Samp led @ 1600

0.80 sec Well dry @ 0.25 gal purged
 0.75 sec Samp led @ 1640

0.75 sec Well dry @ 0.50 gal purged
 1.00 sec Samp led @ 1655

TEMPPH.XLS
4/1/97



Monitoring Data

Project: FERA 02.005
 Date: 2/15/05
 Recorded By: RCM

Project Number: FERA 02.005
 Date: 2/15/05
 Recorded By: RCM

WELL	TIME	TEMP (deg C)	pH	COND. (μ S/cm)	DISSOLVED OXYGEN	TOTAL VOLUME REMOVED	COMMENTS/OBSERVATIONS
MW-2	1333	17.3	6.1	123		2.25	
✓	1342	16.9	6.2	245		3.25	Well dry @ 3.25 gal purged
MW-1	1355	18.4	6.4	227		0.75	7 cm sampled @ 1710
✓	1418	17.5	5.9	399		1.0	1.50 cm Well dry @ 0.75 gal purged
✓	1442	17.5	6.0	326		2.1	2.25 cm sampled @ 1720 odor
✓	1503	17.1	6.0	306		3.2	Sampled @ 1735
✓	1527	18.3	6.5	277		0.50	odor & sheer
✓							1.75 Well dry @ 0.50 gal purged
✓							2.50 Sampled @ 1750

TEMPPH.XLS
 4/1/07

Remediation System Field Data Sheet

Dave's Pit Stop
Sebastopol, California

Apex Envirotech, Inc.

Date of site visit:	1/5/2005				APEX employee: Paul White			
Time of arrival:	09:00				System status upon arrival: Shutdown			
Time of departure:	11:00				Alarm Indications (if shutdown):			
VAPOR EXTRACTION SYSTEM								
Oil Level Check	AWS Level Check	Natural Gas Meter	Hour	Current	Chart	Dilution	No indication for shutdown.	
OK or Low	OK or High	(cu. ft.)	Meter	Time	Flow	Air		
OK Replaced	OK	176,100	5,60	16,304.5	(hours)	(cfm)	(% Open)	
THERMAL OXIDIZER								
Temperature indicating Controller (TIC)	High Limit	Gas Pressure	Regulated	Modulated	AIR SPARGE SYSTEM			
Controller	Actual Temp. (°F)	(psig)	(w.c.)	(w.c.)	Discharge Pressure (psi)	Temperature (°F)	Pressure (psig)	Flow (scfm)
1450	1,460	1800	4.5	35	100	10	85	
VAPOR EXTRACTION WELLS								
Well	Valve Position (% OPEN)	Vacuum ("w.c.)	Well	Valve Position	Well	Valve Position		
VEW-1	0%	—	AS-2 Deep	100	AS-6	100		
VEW-2	0%	—	AS-2 Shallow	0	AS-7	100		
VEW-3	0%	—	AS-3 Deep	100	AS-8	100		
VEW-4	0%	—	AS-3 Shallow	0	FLOWRATES			
MW-1	10%	85	AS-4 Deep	100	Temp. (°F)	Delta PI ("w.c.)	Pressure (± "w.c.)	Flow (scfm)
MW-2	0%	—	AS-4 Shallow	0	SVE BLOWER (THOXINF)	140	0.70	3.0
MW-4	0%	90	AS-5 Deep	100	VEW MANIFOLD	55	0.22	65.3
			AS-5 Shallow	0				21.2
SAMPLES COLLECTED AND SAMPLE TIMES								
Air Sample ID's:	Time		Sampler	(ppmv)		FIELD NOTES		
THOXEFF	10:00		PV	0.5		Replaced blower gear end oil with AEON PD Synthetic oil.		
THOXINF	10:10		PV	2,000		Collected vapor samples.		
VEWMAN	10:20		PW	2,800		Met with PG&E for installation of system meter.		
VEW-1								
VEW-2								
VEW-3								
VEW-4								
MW-1								
MW-2								
MW-4								

Remediation System
Field Data Sheet

Dave's Pit Stop
Sebastopol, California
ERA02.005

Apex Envirotech, Inc.

Date of site visit:	11/19/2005			APEX employee:	Paul White		
Time of arrival:	08:30			System status upon arrival:	Shutdown		
Time of departure:	11:00			Alarm Indications (if shutdown):			
VAPOR EXTRACTION SYSTEM							
Oil Level	AWS Level	Natural Gas	Hour	Current	Chart	Dilution	High Knockout level.
Check	Meter	Flowrate	Meter	Time	Flow	Air	
OK or Low	(cu. ft.)	(cfm)	(hours)	(hours)	(cfm)	(% Open)	
OK	250,100	4,00	6573.8	09:30	715	1	
Thermal Oxidizer							
Temperature Indicating Controller (TIC)	High Limit	Gas	Regulated	Modulated	AIR SPARGE SYSTEM		
Controller	Actual Temp.	Pressure	Gas Pressure	Gas Pressure	Compressor	Temperature	Pressure
(°F)	(°F)	(psig)	(" w.c.)	(" w.c.)	(psi)	(°F)	(psig)
1450	1460	1,800	5.0	35	10	110	62.9
VAPOR EXTRACTION WELLS							
Well	Valve Position	Vacuum	Well	Valve Position	Well	Valve Position	
	(% OPEN)	("w.c.)	AS-2	Deep	AS-6		
VEW-1	0%	—	AS-2	Shallow	AS-7		
VEW-2	0%	—	AS-3	Deep	AS-8		
VEW-3	0%	—	AS-3	Shallow			
VEW-4	0%	—	AS-4	Deep			
MW-1	20%	80	AS-4	Shallow			
MW-2	0%	—	AS-5	Deep			
MW-4	100%	80	AS-5	Shallow			
FLOWRATES							
			Temp. (°F)	Delta PI ("w.c.)	Pressure (± "w.c.)	Flow (scfm)	
			SVE BLOWER (THOXINF)	140	0.65	3.0	62.9
			VEW MANIFOLD	60	0.25	-80.0	22.8
SAMPLES COLLECTED AND SAMPLE TIMES							
Air Sample ID's:		Time	Sampler	PID	FIELD NOTES		
THOXEFF				(ppmv)	** Pumped down AWS drums to drums onsite.		
THOXINF				0	** AWS is VERY SMELLY with sheen.		
VIEWMAN				2,600	Restarted THOX		
VEW-1				3,000	Replaced chart paper.		
VEW-2							
VEW-3							
VEW-4							
MW-1							
MW-2							
MW-4							

Remediation System
Field Data Sheet

Dave's Pit Stop
Sebastopol, California
ERA02.005

Apex Envirotech, Inc.

Date of site visit:	2/1/2005	APEX employee:			Paul White
Time of arrival:	10:00	System status upon arrival:			Operating
Time of departure:					
VAPOR EXTRACTION SYSTEM					
Oil Level	AWS Level	Natural Gas	Hour	Current	Chart
Check	Check	Meter	Meter	Flow	Air
OK or Low	OK or High	(cu. ft.)	(hours)	(cfm)	(% Open)
OK	OK (50%)	358,600	4.20	6,886.1	10.30
					84.0
THermal OXIDIZER					
Temperature Indicating Controller (T1C)	High Limit	Gas	Regulated	Modulated	
Controller	Actual Temp.	Pressure	Gas Pressure	Gas Pressure	
(°F)	(°F)	(psig)	(" w.c.)	(" w.c.)	
1,450	1,460	1,800	4.0	36	90
AIR SPARGE SYSTEM					
Temperature	Pressure	Temperature	Pressure	Flow	
Compressor	(psi)	(°F)	(psig)	(psig)	(scfm)
				10	120
VAPOR EXTRACTION WELLS					
Well	Valve Position	Vacuum	Well	Valve	Valve
	(% OPEN)	("w.c.)	Position	Position	Position
VEW-1	0%	—	AS-2 Deep	100	AS-6
VEW-2	0%	—	AS-2 Shallow	0	AS-7
VEW-3	0%	—	AS-3 Deep	100	AS-8
VEW-4	0%	—	AS-3 Shallow	0	
MW-1	20%	90	AS-4 Deep	100	
MW-2	0%	—	AS-4 Shallow	0	
MW-4	100%	90	AS-5 Deep	100	
			AS-5 Shallow	0	
FLOWRATES					
		Temp. (°F)	Delta PI	Pressure	
		(°w.c.)	(± "w.c.)	(psig)	
SVE BLOWER	168	0.60	2.0		
(THOXINF)					59.0
VEW MANIFOLD	60	0.20	-90		20.1
SAMPLES COLLECTED AND SAMPLE TIMES					
Air Sample ID's:	Time	Sampler	PPID	FIELD NOTES	
THOXEFF	EFF	11:00	PW	Need to get drums pumped - 2 full in system enclosure	
THOXINF	INF	11:10	PW	2 AWS drums.	
VEWMAN	VEWMAN	11:20	PW	Dave Zednick has some at his yard in Santa Rosa.	
VEW-1					
VEW-2					
VEW-3					
VEW-4					
MW-1					
MW-2					
MW-4					

Remediation System
Field Data Sheet

Dave's Pit Stop
Sebastopol, California

Apex Envirotech, Inc.

ERA02.005

Date of site visit:	02/22/05	APEX employee:			Faul White
Time of arrival:	09:00	System status upon arrival:			
Time of departure:	11:30				Shutdown

VAPOR EXTRACTION SYSTEM

Oil Level	AWS Level	Natural Gas Meter	Hour	Current Time	Chart Flow	Dilution	Alarm Indications (if shutdown):
Check	Check	Meter (cu. ft.)	Meter (hours)	Time (hours)	(cfm)	(% Open)	Shutdown for electric meter install.
OK or Low	OK or High						
OK	OK	50%	156,900	42	72011	65.0	5

THERMAL OXIDIZER

Temperature Indicating Controller (TIC)	High Limit	Gas Pressure	Regulated	Modulated
Controller	Actual Temp.	(°F)	(psig)	(w.c.)
1,450	1,457	1,800	4	35

VAPOR EXTRACTION WELLS

Well	Valve Position	Vacuum (% OPEN)	Well Position	Valve Position	Well Position
VEW-1	0%	(w.c.)	AS-2 Deep	100	AS-6
VEW-2	0%	—	AS-2 Shallow	0	AS-7
VEW-3	0%	—	AS-3 Deep	100	AS-8
VEW-4	0%	—	AS-3 Shallow	0	
MW-1	25%	90	AS-4 Deep	100	
MW-2	0%	—	AS-4 Shallow	0	
MW-4	100%	90	AS-5 Deep	100	
			AS-5 Shallow	0	

AIR SPARGE SYSTEM

Compressor	Discharge Pressure (psi)	Temperature (°F)	Pressure (psig)	Flow (scfm)
	11	100	100	

SAMPLES COLLECTED AND SAMPLE TIMES

Air Sample ID's:	Time	Sampler	PID	FIELD NOTES
THOXEFF			0	Restarted system
THOXINF			1,800	
VIEWMAN			2,000	Replaced chart paper.
VEW-1				
VEW-2				
VEW-3				6 full drums onsite.
VEW-4				
MW-1			220	
MW-2				
MW-4			2,900	

Remediation System
Field Data Sheet

Dave's Pit Stop
Sebastopol, California
ERA02.005

Apex Envirotech, Inc.

Date of site visit:	03/03/05	System status upon arrival:			APEX employee:	PCW
Time of arrival:	12:00				Operating	
Time of departure:	14:00				Alarm indications (if shutdown):	
VAPOR EXTRACTION SYSTEM						
Oil Level	AWS Level	Natural Gas	Hour	Current	Chart	Dilution
Check	Check	Meter	Flowrate	Meter	Flow	Air
OK or Low	OK or High	(cu. ft.)	(cfm)	(hours)	(cfm)	(% Open)
OK	OK	526,900	38	1748.0	1200	5
Thermal Oxidizer						
Temperature indicating Controller (TIC)	High Limit	Gas	Regulated	Modulated	Air Sparge System	
Controller	Actual Temp.	Pressure	Gas Pressure	Gas Pressure	Compressor	
(°F)	(°F)	(psig)	(" w.c.)	(" w.c.)	Discharge Pressure	Temperature
1450	1470	1800	4.0	35	(psi)	(°F)
Vapor Extraction Wells						
Well	Valve Position	Vacuum	Well	Valve Position	Well	Valve Position
	(% OPEN)	("w.c.)				
VEW-1	0	--	AS-2 Deep	100	AS-6	100
VEW-2	0	--	AS-2 Shallow	0	AS-7	100
VEW-3	0	--	AS-3 Deep	100	AS-8	100
VEW-4	0	--	AS-3 Shallow	0		
MW-1	25%	90	AS-4 Deep	100		
MW-2	0	--	AS-4 Shallow	0		
MW-4	100%	90	AS-5 Deep	100		
			AS-5 Shallow	0		
Samples Collected and Sample Times						
Air Sample ID's:		Time	Sampler	PID	Field Notes	
THOXEFF	EFF	13:00	PW	(ppmv)		
THOXINF	INF	13:10	PW	0	Lubricated blower drive end with NLGI grease	
VIEWMAN	VIEWMAN	13:20	PW	1,729		
VEW-1				5,120		
VEW-2						
VEW-3						
VEW-4						
MW-1						
MW-2						
MW-4						
					150	
					> 10,000	

Remediation System
Field Data Sheet

Dave's Pit Stop
Sebastopol, California
ERA02.005

Apex Envirotech, Inc.

Date of site visit:	3/16/2005	APEX employee:			POW
Time of arrival:	13:00	System status upon arrival:			Operating
Time of departure:	15:00				Alarm Indications (if shutdown):
VAPOR EXTRACTION SYSTEM					
Oil Level	AWS Level	Natural Gas	Hour	Current	Chart
Check	Meter	Flowrate	Meter	Flow	Air
OK or Low	(cu. ft.)	(cm)	(hours)	(cfm)	(% Open)
OK	627,600	37	17:32	69.4	5
THERMAL OXIDIZER					
Temperature Indicating Controller (TIC)	High Limit	Gas	Regulated	Modulated	
Controller	Actual Temp.	Pressure	Gas Pressure	Gas Pressure	
(°F)	(°F)	(psig)	(" w.c.)	(" w.c.)	
1450	1470	1800	4	36	10
VAPOR EXTRACTION WELLS					
Well	Valve Position	Vacuum	Well	Valve	Valve
	(% OPEN)	("w.c.)	Position	Well	Position
VEW-1	0	AS-2 Deep	100	AS-6	100
VEW-2	0	AS-2 Shallow	0	AS-7	100
VEW-3	0	AS-3 Deep	100	AS-8	100
VEW-4	0	AS-3 Shallow	0		
MW-1	25%	AS-4 Deep	100		
MW-2	0	AS-4 Shallow	0		
MW-4	100%	AS-5 Deep	100		
		AS-5 Shallow	0		
AIR SPARGE WELLS					
Well	Valve Position	Vacuum	Well	Valve	Valve
	(% OPEN)	("w.c.)	Position	Well	Position
AS-2	0	AS-2 Deep	100	AS-6	100
AS-3	0	AS-2 Shallow	0	AS-7	100
AS-4	0	AS-3 Deep	100	AS-8	100
AS-5	0	AS-3 Shallow	0		
SVE BLOWER		AS-4 Deep	100		
(THOXINF)		AS-4 Shallow	0		
VIEW		AS-5 Deep	100		
MANIFOLD		AS-5 Shallow	0		
FLOWRATES					
			Temp. (°F)	Delta PI ("w.c.)	Pressure (psig)
					Flow (scfm)
SVE BLOWER			165	0.50	2.0
(THOXINF)					54.0
VIEW					
MANIFOLD					
SAMPLES COLLECTED AND SAMPLE TIMES					
Air Sample ID's:	Time	Sampler	PID	FIELD NOTES	
THOXEFF			(ppmv)	Found AWS pump stuck on. ISI 851 switch contacts are bad.	
THOXINF			0	Need to replace switch, left pump in off	
VIEWMAN					
VIEW-1					
VIEW-2					
VIEW-3					
VIEW-4					
MW-1					
MW-2					
MW-4					

APPENDIX C

**LABORATORY ANALYTICAL REPORT AND
CHAIN-OF-CUSTODY FORM**

CALIFORNIA LABORATORY SERVICES

CLS ID. NO.

C030554

Report To:

Name and Address		Client Job Number		CHAIN OF CUSTODY		ANALYSIS REQUESTED		GEOTRACKER	
Apex Envirotech, Inc.		ERA02.005-QM		Destination Laboratory		T T B M T A B		EDF REPORT X YES <input type="checkbox"/> NO	
11244 Pyrites Wy, Gold River, CA 95670				CLS (916) 638-7301 3249 Fitzgerald Road Rancho Cordova, CA 95742 www.californialab.com		H H E B M A S d X E E		GLOBAL ID: T069970169	
Project Manager Kasey Jones	Sampled By <i>L Morgan</i>	Job Description 1" qtr water	<input checked="" type="checkbox"/> OTHER	FIELD CONDITIONS		PRESERVATIVES		FIELD CONDITIONS	
Project Name Dave's Pit Stop				COMPOSITE		8 8 8 8 8 8 0 0 0 2 2 6 1 1 0 2 2 6 5 5 2 6 6 0 0 0 0 0 0 0			
Site Location 7200 Headlands Ave, Sebastopol		SAMPLE IDENTIFICATION		FIELD ID.	MATRIX	CONTAINER NO.	TYPE	TURNAROUND TIME IN DAYS	
2/15/05	H20	MW-1	MW-1	3/1	V/A	1	X X X X X	1	1
2/10	H2O	MW-2	MW-2	3/1	V/A	1	X X X X X	2	2
1/10	MW-3	MW-3	MW-3	3/1	V/A	1	X X X X X	5	5
1/15/05	MW-4	MW-4	MW-4	3/1	V/A	1	X X X X X	10	10
MW-5	MW-5	MW-5	MW-5	3/1	V/A	1	X X X X X	0.50 ug/L	0.50 ug/L
2/15/05	1600	MW-6	MW-6	3/1	V/A	1	X X X X X	2 years w/ bubbles form	2 years w/ bubbles form
1655	MW-7	MW-7	MW-7	3/1	V/A	1	X X X X X	No sample form	No sample form
1640	MW-8	MW-8	MW-8	3/1	V/A	1	X X X X X	1 vac w/bubbles form	1 vac w/bubbles form
1735	MW-9	MW-9	MW-9	3/1	V/A	1	X X X X X	X	X
SUSPECTED CONSTITUENTS								INVOICE TO:	
REINQUISITION BY (Signature)		PRINT NAME/COMPANY		DATE/TIME		RECEIVED BY (Signature)		PRINT NAME/COMPANY	
<i>John D. Morgan</i>		Bio-Vigilant Annex		2/15/05 11:15 AM		<i>John D. Morgan</i>		C030554	
RECEIVED AT LAB: 2/15/05		DATE/TIME 2/16/05 11:10 AM		CONDITIONS/COMMENTS:					
SHIPPED BY: UPS		<input type="checkbox"/> FED EX <input type="checkbox"/> OTHER						AIR BILL #	

CALIFORNIA LABORATORY SERVICES

3249 Fitzgerald Road Rancho Cordova, CA 95742

February 23, 2005

CLS Work Order #: COB0554
COC #: None


Kasey Jones
APEX Envirotech Inc. - Gold River
11244 Pyrites Way
Gold River, CA 95670

Project Name: Dave's Pit Stop

Enclosed are the results of analyses for samples received by the laboratory on 02/16/05 16:10.
Samples were analyzed pursuant to client request utilizing EPA or other ELAP approved
methodologies. I certify that the results are in compliance both technically and for completeness.

Analytical results are attached to this letter. Please call if we can provide additional assistance.

Sincerely,



James Liang, Ph.D.
Laboratory Director

CA DOHS ELAP Accreditation/Registration number 1233

CALIFORNIA LABORATORY SERVICES

02/23/05 10:14

APEX Envirotech Inc - Gold River 11244 Pyrites Way Gold River, CA 95670	Project: Dave's Pit Stop Project Number: ERA02 005-QM Project Manager: Kasey Jones	CLS Work Order #: COB0554 COC #: None
---	--	--

Extractable Petroleum Hydrocarbons by EPA Method 8015M

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
MW-1 (COB0554-01) Water Sampled: 02/15/05 17:20 Received: 02/16/05 16:10									
Diesel	ND	0.050	mg/L	1	CO01294	02/18/05	02/21/05	EPA 8015M	
MW-2 (COB0554-02) Water Sampled: 02/15/05 17:10 Received: 02/16/05 16:10									
Diesel	0.12	0.050	mg/L	1	CO01294	02/18/05	02/21/05	EPA 8015M	DSL-1
MW-3 (COB0554-03) Water Sampled: 02/15/05 16:10 Received: 02/16/05 16:10									
Diesel	ND	0.050	mg/L	1	CO01294	02/18/05	02/21/05	EPA 8015M	
MW-4 (COB0554-04) Water Sampled: 02/15/05 17:50 Received: 02/16/05 16:10									
Diesel	42	1.0	mg/L	20	CO01294	02/18/05	02/21/05	EPA 8015M	
MW-6 (COB0554-05) Water Sampled: 02/15/05 16:00 Received: 02/16/05 16:10									
Diesel	ND	0.050	mg/L	1	CO01294	02/18/05	02/21/05	EPA 8015M	
MW-7 (COB0554-06) Water Sampled: 02/15/05 16:55 Received: 02/16/05 16:10									
Diesel	ND	0.050	mg/L	1	CO01294	02/18/05	02/21/05	EPA 8015M	
MW-8 (COB0554-07) Water Sampled: 02/15/05 16:40 Received: 02/16/05 16:10									
Diesel	ND	0.050	mg/L	1	CO01294	02/18/05	02/21/05	EPA 8015M	
MW-9 (COB0554-08) Water Sampled: 02/15/05 17:35 Received: 02/16/05 16:10									
Diesel	0.22	0.050	mg/L	1	CO01294	02/18/05	02/21/05	EPA 8015M	DSL-1

CA DOHS ELAP Accreditation/Registration Number 1233

CALIFORNIA LABORATORY SERVICES

02/23/05 10:14

APEX Envirotech Inc - Gold River 11244 Pyrites Way Gold River, CA 95670	Project: Dave's Pit Stop Project Number: ERA02.005-QM Project Manager: Kasey Jones	CLS Work Order #: COB0554 COC #: None
---	--	--

Gas/BTEX by GC PID/FID

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
MW-1 (COB0554-01) Water Sampled: 02/15/05 17:20 Received: 02/16/05 16:10									
Gasoline	ND	50	µg/L	1	CO01282	02/17/05	02/17/05	8015M/8021B	
Benzene	ND	0.50	"	"	"	"	"	"	"
Toluene	0.58	0.50	"	"	"	"	"	"	"
Ethylbenzene	ND	0.50	"	"	"	"	"	"	"
Xylenes (total)	1.0	1.0	"	"	"	"	"	"	"
<i>Surrogate: o-Chlorotoluene (Gas)</i>	94.5 %	65-135		"	"	"	"	"	
MW-2 (COB0554-02) Water Sampled: 02/15/05 17:10 Received: 02/16/05 16:10									
Gasoline	230	50	µg/L	1	CO01282	02/17/05	02/17/05	8015M/8021B	GAS-1
Benzene	ND	0.50	"	"	"	"	"	"	"
Toluene	4.1	0.50	"	"	"	"	"	"	"
Ethylbenzene	0.91	0.50	"	"	"	"	"	"	"
Xylenes (total)	1.8	1.0	"	"	"	"	"	"	"
<i>Surrogate: o-Chlorotoluene (Gas)</i>	99.5 %	65-135		"	"	"	"	"	
MW-3 (COB0554-03) Water Sampled: 02/15/05 16:10 Received: 02/16/05 16:10									
Gasoline	ND	50	µg/L	1	CO01292	02/18/05	02/18/05	8015M/8021B	
Benzene	ND	0.50	"	"	"	"	"	"	"
Toluene	ND	0.50	"	"	"	"	"	"	"
Ethylbenzene	ND	0.50	"	"	"	"	"	"	"
Xylenes (total)	ND	1.0	"	"	"	"	"	"	"
<i>Surrogate: o-Chlorotoluene (Gas)</i>	94.0 %	65-135		"	"	"	"	"	
MW-4 (COB0554-04) Water Sampled: 02/15/05 17:50 Received: 02/16/05 16:10									
Gasoline	71000	25000	µg/L	500	CO01292	02/18/05	02/18/05	8015M/8021B	
Benzene	1600	250	"	"	"	"	"	"	"
Toluene	11000	250	"	"	"	"	"	"	"
Ethylbenzene	850	250	"	"	"	"	"	"	"
Xylenes (total)	15000	500	"	"	"	"	"	"	"
<i>Surrogate: o-Chlorotoluene (Gas)</i>	102 %	65-135		"	"	"	"	"	

CA DOHS ELAP Accreditation/Registration Number 1233

CALIFORNIA LABORATORY SERVICES

02/23/05 10:14

APEX Envirotech Inc - Gold River 11244 Pyrites Way Gold River, CA 95670	Project: Dave's Pit Stop Project Number: ERA02.005-QM Project Manager: Kasey Jones	CLS Work Order #: COB0554 COC #: None
---	--	--

Gas/BTEX by GC PID/FID

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
MW-6 (COB0554-05) Water Sampled: 02/15/05 16:00 Received: 02/16/05 16:10									
Gasoline	ND	50	µg/L	1	CO01292	02/18/05	02/18/05	8015M/8021B	
Benzene	ND	0.50	"	"	"	"	"	"	
Toluene	ND	0.50	"	"	"	"	"	"	
Ethylbenzene	ND	0.50	"	"	"	"	"	"	
Xylenes (total)	ND	1.0	"	"	"	"	"	"	
<i>Surrogate o-Chlorotoluene (Gas)</i>		93.0 %	65-135	"	"	"	"	"	
MW-7 (COB0554-06) Water Sampled: 02/15/05 16:55 Received: 02/16/05 16:10									
Gasoline	ND	50	µg/L	1	CO01292	02/18/05	02/18/05	8015M/8021B	
Benzene	ND	0.50	"	"	"	"	"	"	
Toluene	0.55	0.50	"	"	"	"	"	"	
Ethylbenzene	ND	0.50	"	"	"	"	"	"	
Xylenes (total)	ND	1.0	"	"	"	"	"	"	
<i>Surrogate o-Chlorotoluene (Gas)</i>		94.5 %	65-135	"	"	"	"	"	
MW-8 (COB0554-07) Water Sampled: 02/15/05 16:40 Received: 02/16/05 16:10									
Gasoline	ND	50	µg/L	1	CO01292	02/18/05	02/18/05	8015M/8021B	
Benzene	ND	0.50	"	"	"	"	"	"	
Toluene	ND	0.50	"	"	"	"	"	"	
Ethylbenzene	ND	0.50	"	"	"	"	"	"	
Xylenes (total)	ND	1.0	"	"	"	"	"	"	
<i>Surrogate o-Chlorotoluene (Gas)</i>		91.0 %	65-135	"	"	"	"	"	
MW-9 (COB0554-08) Water Sampled: 02/15/05 17:35 Received: 02/16/05 16:10									
Gasoline	4400	2500	µg/L	50	CO01292	02/18/05	02/18/05	8015M/8021B	GAS-1
Benzene	2000	25	"	0	"	"	"	"	
Toluene	36	25	0	"	"	"	"	"	
Ethylbenzene	38	25	"	"	"	"	"	"	
Xylenes (total)	120	50	"	"	"	"	"	"	
<i>Surrogate o-Chlorotoluene (Gas)</i>		100 %	65-135	"	"	"	"	"	

CA DOHS ELAP Accreditation/Registration Number 1233

CALIFORNIA LABORATORY SERVICES

02/23/05 10:14

APEX Envirotech Inc. - Gold River 11244 Pyrites Way Gold River, CA 95670	Project: Dave's Pit Stop Project Number: ERA02 005-QM Project Manager: Kasey Jones	CLS Work Order #: COB0554 COC #: None
--	--	--

Volatile Organic Compounds by EPA Method 8260B

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
MW-1 (COB0554-01) Water Sampled: 02/15/05 17:20 Received: 02/16/05 16:10									
Methyl tert-butyl ether	ND	0.50	µg/L	1	CO01251	02/17/05	02/17/05	EPA 8260B	
tert-Amyl methyl ether	ND	0.50	"	"	"	"	"	"	"
Tert-butyl alcohol	ND	5.0	"	"	"	"	"	"	"
<i>Surrogate Toluene-d8</i> 102 % 72-125 " " " "									
MW-2 (COB0554-02) Water Sampled: 02/15/05 17:10 Received: 02/16/05 16:10									
Methyl tert-butyl ether	9.8	0.50	µg/L	1	CO01251	02/17/05	02/17/05	EPA 8260B	
tert-Amyl methyl ether	ND	0.50	"	"	"	"	"	"	"
Tert-butyl alcohol	ND	5.0	"	"	"	"	"	"	"
<i>Surrogate Toluene-d8</i> 103 % 72-125 " " " "									
MW-3 (COB0554-03) Water Sampled: 02/15/05 16:10 Received: 02/16/05 16:10									
Methyl tert-butyl ether	ND	0.50	µg/L	1	CO01251	02/17/05	02/17/05	EPA 8260B	
tert-Amyl methyl ether	ND	0.50	"	"	"	"	"	"	"
Tert-butyl alcohol	ND	5.0	"	"	"	"	"	"	"
<i>Surrogate Toluene-d8</i> 101 % 72-125 " " " "									
MW-4 (COB0554-04) Water Sampled: 02/15/05 17:50 Received: 02/16/05 16:10									
Methyl tert-butyl ether	42	2.5	µg/L	5	CO01251	02/17/05	02/17/05	EPA 8260B	
tert-Amyl methyl ether	110	2.5	"	"	"	"	"	"	"
Tert-butyl alcohol	2100	25	"	"	"	"	"	"	"
<i>Surrogate Toluene-d8</i> 106 % 72-125 " " " "									
MW-6 (COB0554-05) Water Sampled: 02/15/05 16:00 Received: 02/16/05 16:10									
Methyl tert-butyl ether	ND	0.50	µg/L	1	CO01251	02/17/05	02/17/05	EPA 8260B	
tert-Amyl methyl ether	ND	0.50	"	"	"	"	"	"	"
Tert-butyl alcohol	ND	5.0	"	"	"	"	"	"	"
<i>Surrogate Toluene-d8</i> 102 % 72-125 " " " "									

CA DOHS ELAP Accreditation/Registration Number 1233

CALIFORNIA LABORATORY SERVICES

02/23/05 10:14

APEX Envirotech Inc. - Gold River 11244 Pyrites Way Gold River, CA 95670	Project: Dave's Pit Stop Project Number: ERA02.005-QM Project Manager: Kasey Jones	CLS Work Order #: COB0554 COC #: None
--	--	--

Volatile Organic Compounds by EPA Method 8260B

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
MW-7 (COB0554-06) Water Sampled: 02/15/05 16:55 Received: 02/16/05 16:10									
Methyl tert-butyl ether	ND	0.50	µg/L	1	CO01251	02/17/05	02/17/05	EPA 8260B	
tert-Amyl methyl ether	ND	0.50	"	"	"	"	"	"	"
Tert-butyl alcohol	ND	5.0	"	"	"	"	"	"	"
<i>Surrogate: Toluene-d8</i> 100 % 72-125 " " " "									
MW-8 (COB0554-07) Water Sampled: 02/15/05 16:40 Received: 02/16/05 16:10									
Methyl tert-butyl ether	ND	0.50	µg/L	1	CO01251	02/17/05	02/17/05	EPA 8260B	
tert-Amyl methyl ether	ND	0.50	"	"	"	"	"	"	"
Tert-butyl alcohol	ND	5.0	"	"	"	"	"	"	"
<i>Surrogate: Toluene-d8</i> 102 % 72-125 " " " "									
MW-9 (COB0554-08) Water Sampled: 02/15/05 17:35 Received: 02/16/05 16:10									
Methyl tert-butyl ether	210	2.5	µg/L	5	CO01251	02/17/05	02/17/05	EPA 8260B	
tert-Amyl methyl ether	ND	2.5	"	"	"	"	"	"	"
Tert-butyl alcohol	ND	25	"	"	"	"	"	"	"
<i>Surrogate: Toluene-d8</i> 105 % 72-125 " " " "									

CA DOHS ELAP Accreditation/Registration Number 1233

CALIFORNIA LABORATORY SERVICES

02/23/05 10:14

APEX Envirotech Inc. - Gold River 11244 Pyrites Way Gold River, CA 95670	Project: Dave's Pit Stop Project Number: ERA02 005-QM Project Manager: Kasey Jones	CLS Work Order #: COB0554 COC #: None
--	--	--

Extractable Petroleum Hydrocarbons by EPA Method 8015M - Quality Control

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Batch CO01294 - EPA 3510B GCNV										
Blank (CO01294-BLK1)										
Diesel	ND	0 050	mg/L							
Motor Oil	ND	0 050	"							
LCS (CO01294-BS1)										
Diesel	2 70	0 050	mg/L	2 50		108	65-135			
LCS Dup (CO01294-BSD1)										
Diesel	2 72	0 050	mg/L	2 50		109	65-135	0 738	30	

CA DOHS ELAP Accreditation/Registration Number 1233

CALIFORNIA LABORATORY SERVICES

02/23/05 10:14

APEX Envirotech Inc - Gold River 11244 Pyrites Way Gold River, CA 95670	Project: Dave's Pit Stop Project Number: ERA02 005-QM Project Manager: Kasey Jones	CLS Work Order #: COB0554 COC #: None
---	--	--

Gas/BTEX by GC PID/FID - Quality Control

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
---------	--------	-----------------	-------	-------------	---------------	------	-------------	-----	-----------	-------

Batch CO01282 - EPA 5030 Water GC

Blank (CO01282-BLK1)		Prepared & Analyzed: 02/17/05					
Gasoline	ND	50	µg/L				
Benzene	ND	0.50	"				
Toluene	ND	0.50	"				
Ethylbenzene	ND	0.50	"				
Xylenes (total)	ND	1.0	"				
Surrogate. o-Chlorotoluene (BTEX)	20.4		"	20.0	102	65-135	
Surrogate. o-Chlorotoluene (Gas)	20.0		"	20.0	100	65-135	

LCS (CO01282-BS1)

LCS (CO01282-BS1)		Prepared & Analyzed: 02/17/05					
Gasoline	529	50	µg/L	500	106	65-135	
Surrogate. o-Chlorotoluene (Gas)	21.8		"	20.0	109	65-135	

LCS Dup (CO01282-BSD1)

LCS Dup (CO01282-BSD1)		Prepared & Analyzed: 02/17/05					
Gasoline	391	50	µg/L	500	78.2	65-135	30.0
Surrogate. o-Chlorotoluene (Gas)	16.3		"	20.0	81.5	65-135	30

Batch CO01292 - EPA 5030 Water GC

Blank (CO01292-BLK1)		Prepared & Analyzed: 02/18/05					
Gasoline	ND	50	µg/L				
Benzene	ND	0.50	"				
Toluene	ND	0.50	"				
Ethylbenzene	ND	0.50	"				
Xylenes (total)	ND	1.0	"				
Surrogate. o-Chlorotoluene (BTEX)	20.5		"	20.0	102	65-135	
Surrogate. o-Chlorotoluene (Gas)	19.9		"	20.0	99.5	65-135	

CA DOHS ELAP Accreditation/Registration Number 1233

CALIFORNIA LABORATORY SERVICES

02/23/05 10:14

APEX Envirotech Inc - Gold River 11244 Pyrites Way Gold River, CA 95670	Project: Dave's Pit Stop Project Number: ERA02.005-QM Project Manager: Kasey Jones	CLS Work Order #: COB0554 COC #: None
---	--	--

Gas/BTEX by GC PID/FID - Quality Control

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD RPD	RPD Limit	Notes
Batch CO01292 - EPA 5030 Water GC										
LCS (CO01292-BS1)										
Prepared & Analyzed: 02/18/05										
Benzene	22.6	0.50	µg/L	20.0		113	70-140			
Toluene	21.9	0.50	"	20.0		110	70-140			
Ethylbenzene	21.2	0.50	"	20.0		106	70-140			
Xylenes (total)	64.9	1.0	"	60.0		108	70-140			
Surrogate: o-Chlorotoluene (BTEX)	20.0		"	20.0		100	65-135			
LCS Dup (CO01292-BSD1)										
Prepared & Analyzed: 02/18/05										
Benzene	23.2	0.50	µg/L	20.0		116	70-140	2.62	30	
Toluene	21.0	0.50	"	20.0		105	70-140	4.20	30	
Ethylbenzene	20.5	0.50	"	20.0		102	70-140	3.36	30	
Xylenes (total)	62.7	1.0	"	60.0		104	70-140	3.45	30	
Surrogate: o-Chlorotoluene (BTEX)	20.3		"	20.0		102	65-135			
Matrix Spike (CO01292-MS1)										
Source: COB0554-07 Prepared & Analyzed: 02/18/05										
Benzene	20.8	0.50	µg/L	20.0	ND	104	60-140			
Toluene	20.4	0.50	"	20.0	ND	102	60-140			
Ethylbenzene	19.7	0.50	"	20.0	ND	98.5	60-140			
Xylenes (total)	60.4	1.0	"	60.0	ND	101	60-140			
Surrogate: o-Chlorotoluene (BTEX)	19.7		"	20.0		98.5	65-135			
Matrix Spike Dup (CO01292-MSD1)										
Source: COB0554-07 Prepared & Analyzed: 02/18/05										
Benzene	25.2	0.50	µg/L	20.0	ND	126	60-140	19.1	30	
Toluene	21.4	0.50	"	20.0	ND	107	60-140	4.78	30	
Ethylbenzene	20.8	0.50	"	20.0	ND	104	60-140	5.43	30	
Xylenes (total)	63.8	1.0	"	60.0	ND	106	60-140	5.48	30	
Surrogate: o-Chlorotoluene (BTEX)	20.0		"	20.0		100	65-135			

CA DOHS ELAP Accreditation/Registration Number 1233

CALIFORNIA LABORATORY SERVICES

02/23/05 10:14

APEX Envirotech Inc. - Gold River 11244 Pyrites Way Gold River, CA 95670	Project: Dave's Pit Stop Project Number: ERA02 005-QM Project Manager: Kasey Jones	CLS Work Order #: COB0554 COC #: None
--	--	--

Volatile Organic Compounds by EPA Method 8260B - Quality Control

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Batch CO01251 - EPA 5030 Water MS										
Blank (CO01251-BLK1)										
Prepared & Analyzed: 02/17/05										
Di-isopropyl ether	ND	0.50	µg/L							
Ethyl tert-butyl ether	ND	0.50	"							
Methyl tert-butyl ether	ND	0.50	"							
tert-Amyl methyl ether	ND	0.50	"							
Tert-butyl alcohol	ND	5.0	"							
<i>Surrogate: Toluene-d8</i>	10.2		"	10.0		102	72-125			
LCS (CO01251-BS1)										
Prepared & Analyzed: 02/17/05										
Methyl tert-butyl ether	19.2	0.50	µg/L	20.0		96.0	52-130			
<i>Surrogate: Toluene-d8</i>	10.8		"	10.0		108	72-125			
LCS Dup (CO01251-BSD1)										
Prepared & Analyzed: 02/17/05										
Methyl tert-butyl ether	20.8	0.50	µg/L	20.0		104	52-130	8.00	30	
<i>Surrogate: Toluene-d8</i>	10.8		"	10.0		108	72-125			

CA DOHS ELAP Accreditation/Registration Number 1233

CALIFORNIA LABORATORY SERVICES

02/23/05 10:14

APEX Envirotech Inc - Gold River 11244 Pyrites Way Gold River, CA 95670	Project: Dave's Pit Stop Project Number: ERA02 005-QM Project Manager: Kasey Jones	CLS Work Order #: COB0554 COC #: None
---	--	--

Notes and Definitions

- GAS-1 Although sample contains compounds in the retention time range associated with gasoline, the chromatogram was not consistent with the expected chromatographic pattern or "fingerprint". However, the reported concentration is based on gasoline.
- DSL-1 Although sample contains compounds in the retention time range associated with diesel, the chromatogram was not consistent with the expected chromatographic pattern or "fingerprint". However, the reported concentration is based on diesel.
- DET Analyte DETECTED
- ND Analyte NOT DETECTED at or above the reporting limit
- NR Not Reported
- dry Sample results reported on a dry weight basis
- RPD Relative Percent Difference



Report Number : 42651

Date : 3/10/2005

Richard Johnson
Apex Envirotech Inc.
11244 Pyrites Way
Gold River, CA 95670-4481

Subject : 3 Vapor Samples
Project Name : Dave's Pit Stop
Project Number : ERA02.005
P.O. Number : ERA02.005

Dear Mr. Johnson,

Chemical analysis of the samples referenced above has been completed. Summaries of the data are contained on the following pages. Sample(s) were received under documented chain-of-custody. US EPA protocols for sample storage and preservation were followed.

Kiff Analytical is certified by the State of California (# 2236). If you have any questions regarding procedures or results, please call me at 530-297-4800.

Sincerely,

A handwritten signature in black ink that reads "Joel Kiff".

Joel Kiff



Report Number : 42651

Date : 3/10/2005

Project Name : Dave's Pit Stop

Project Number : ERA02.005

Sample : THOXEFF

Matrix : Air

Lab Number : 42651-01

Sample Date : 3/3/2005

Parameter	Measured Value	Method Reporting Limit	Units	Analysis Method	Date Analyzed
Benzene	< 0.050	0.050	ppmv	EPA 8260B	3/4/2005
Toluene	< 0.050	0.050	ppmv	EPA 8260B	3/4/2005
Ethylbenzene	< 0.050	0.050	ppmv	EPA 8260B	3/4/2005
Total Xylenes	< 0.050	0.050	ppmv	EPA 8260B	3/4/2005
Methyl-t-butyl ether (MTBE)	< 0.10	0.10	ppmv	EPA 8260B	3/4/2005
TPH as Gasoline	< 5.0	5.0	ppmv	EPA 8260B	3/4/2005
Toluene - d8 (Surr)	97.8		% Recovery	EPA 8260B	3/4/2005
4-Bromofluorobenzene (Surr)	106		% Recovery	EPA 8260B	3/4/2005

Sample : VEWMAN

Matrix : Air

Lab Number : 42651-02

Sample Date : 3/3/2005

Parameter	Measured Value	Method Reporting Limit	Units	Analysis Method	Date Analyzed
Benzene	23	0.40	ppmv	EPA 8260B	3/5/2005
Toluene	200	0.40	ppmv	EPA 8260B	3/5/2005
Ethylbenzene	36	0.30	ppmv	EPA 8260B	3/5/2005
Total Xylenes	180	0.60	ppmv	EPA 8260B	3/4/2005
Methyl-t-butyl ether (MTBE)	< 0.40	0.40	ppmv	EPA 8260B	3/5/2005
TPH as Gasoline	2900	70	ppmv	EPA 8260B	3/4/2005
Toluene - d8 (Surr)	96.4		% Recovery	EPA 8260B	3/5/2005
4-Bromofluorobenzene (Surr)	97.0		% Recovery	EPA 8260B	3/5/2005

Approved By:

Jocel Kiff

2795 2nd St., Suite 300 Davis, CA 95616 530-297-4800



Report Number : 42651

Date : 3/10/2005

Project Name : Dave's Pit Stop

Project Number : ERA02.005

Sample : THOXINF

Matrix : Air

Lab Number : 42651-03

Sample Date : 3/3/2005

Parameter	Measured Value	Method Reporting Limit	Units	Analysis Method	Date Analyzed
Benzene	8.8	0.40	ppmv	EPA 8260B	3/4/2005
Toluene	87	0.30	ppmv	EPA 8260B	3/4/2005
Ethylbenzene	22	0.25	ppmv	EPA 8260B	3/4/2005
Total Xylenes	120	0.25	ppmv	EPA 8260B	3/4/2005
Methyl-t-butyl ether (MTBE)	< 0.30	0.30	ppmv	EPA 8260B	3/4/2005
TPH as Gasoline	1500	30	ppmv	EPA 8260B	3/4/2005
Toluene - d8 (Surr)	96.4		% Recovery	EPA 8260B	3/4/2005
4-Bromofluorobenzene (Surr)	92.3		% Recovery	EPA 8260B	3/4/2005

Approved By:

Joel Kiff

2795 2nd St., Suite 300 Davis, CA 95616 530-297-4800



KIFF
ANALYTICAL LLC
2795 2nd Street Suite 300
Davis, CA 95616
Lab: 530.297.4800
Fax: 530.297.4808

Project Contact (Hardcopy or PDF To):

Rich Johnson
Company / Address:

1124 Pyrites Way, Gold River, CA 95670
Phone No.: (916) 851-0174 Fax No.: (916) 851-0177
Project Number: ERA02.005 P.O. No.: ERA02.005
Project Name: Dave's Pit Stop
Project Address: 7200 Healdsburg Ave., Sebastopol, CA 95472

California EDF Report? Yes No

Chain-of-Custody Record and Analysis Request

Analysis Request									
Sampling Company Log Code:									
Global ID:									
EDF Deliverable To (Email Address):									
Sampler Signature:									
Sampling	Container	Preservative	Matrix						
				WATER					
				SOLI					
				VAPOR					
				NONE					
				HCl					
				HNO ₃					
				TEDLAR					
				POLY					
				SLEEVE					
				40 ml VOA					
Sample Designation	FPT Name	Date	Time						
THOXEFF	VEFF	3-3-05	13:00						
YEWMAN THOME	VINF	3-3-05	13:20						
THOXINF		3-3-05	13:10						

Relinquished by:	Date	Time	Received by:	
<i>[Signature]</i>	3-3-05	17:00		
Relinquished by:	Date	Time	Received by:	
<i>[Signature]</i>				
Relinquished by:	Date	Time	Received by Laboratory:	BILL APXTECH
	03/05/05	13:00	<i>[Signature]</i>	

Remarks:

No EDF ON THOX/INF

Bill to:



Report Number : 42151

Date : 2/2/2005

Richard Johnson
Apex Envirotech Inc.
11244 Pyrites Way
Gold River, CA 95670-4481

Subject : 3 Vapor Samples
Project Name : Dave's Pit Stop
Project Number : ERA02.005
P.O. Number : ERA02.005

Dear Mr. Johnson,

Chemical analysis of the samples referenced above has been completed. Summaries of the data are contained on the following pages. Sample(s) were received under documented chain-of-custody US EPA protocols for sample storage and preservation were followed.

Kiff Analytical is certified by the State of California (# 2236). If you have any questions regarding procedures or results, please call me at 530-297-4800.

Sincerely,

A handwritten signature in black ink that reads "Joel Kiff".

Joel Kiff



Report Number : 42151

Date : 2/2/2005

Project Name : Dave's Pit Stop

Project Number : ERA02.005

Sample : THOXEFF

Matrix : Air

Lab Number : 42151-01

Sample Date : 2/1/2005

Parameter	Measured Value	Method Reporting Limit	Units	Analysis Method	Date Analyzed
Benzene	< 0.050	0.050	ppmv	EPA 8260B	2/2/2005
Toluene	< 0.050	0.050	ppmv	EPA 8260B	2/2/2005
Ethylbenzene	< 0.050	0.050	ppmv	EPA 8260B	2/2/2005
Total Xylenes	< 0.050	0.050	ppmv	EPA 8260B	2/2/2005
Methyl-t-butyl ether (MTBE)	< 0.10	0.10	ppmv	EPA 8260B	2/2/2005
TPH as Gasoline	< 5.0	5.0	ppmv	EPA 8260B	2/2/2005
Toluene - d8 (Surr)	98.3		% Recovery	EPA 8260B	2/2/2005
4-Bromofluorobenzene (Surr)	99.1		% Recovery	EPA 8260B	2/2/2005

Sample : THOXINF

Matrix : Air

Lab Number : 42151-02

Sample Date : 2/1/2005

Parameter	Measured Value	Method Reporting Limit	Units	Analysis Method	Date Analyzed
Benzene	11	0.30	ppmv	EPA 8260B	2/2/2005
Toluene	85	0.25	ppmv	EPA 8260B	2/2/2005
Ethylbenzene	19	0.25	ppmv	EPA 8260B	2/2/2005
Total Xylenes	99	0.25	ppmv	EPA 8260B	2/2/2005
Methyl-t-butyl ether (MTBE)	< 0.30	0.30	ppmv	EPA 8260B	2/2/2005
TPH as Gasoline	1500	25	ppmv	EPA 8260B	2/2/2005
Toluene - d8 (Surr)	96.6		% Recovery	EPA 8260B	2/2/2005
4-Bromofluorobenzene (Surr)	97.4		% Recovery	EPA 8260B	2/2/2005

Approved By:

Joel Kiff

2795 2nd St., Suite 300 Davis, CA 95616 530-297-4800



Report Number : 42151

Date : 2/2/2005

Project Name : **Dave's Pit Stop**

Project Number : **ERA02.005**

Sample : **VEWMAN**

Matrix : Air

Lab Number : 42151-03

Sample Date : 2/1/2005

Parameter	Measured Value	Method Reporting Limit	Units	Analysis Method	Date Analyzed
Benzene	39	0.80	ppmv	EPA 8260B	2/2/2005
Toluene	280	0.70	ppmv	EPA 8260B	2/2/2005
Ethylbenzene	57	0.60	ppmv	EPA 8260B	2/2/2005
Total Xylenes	280	0.60	ppmv	EPA 8260B	2/2/2005
Methyl-t-butyl ether (MTBE)	< 0.70	0.70	ppmv	EPA 8260B	2/2/2005
TPH as Gasoline	4800	60	ppmv	EPA 8260B	2/2/2005
Toluene - d8 (Surr)	94.3		% Recovery	EPA 8260B	2/2/2005
4-Bromofluorobenzene (Surr)	98.7		% Recovery	EPA 8260B	2/2/2005

Approved By:

Joe Kiff

2795 2nd St., Suite 300 Davis, CA 95616 530-297-4800



**2795 2nd Street Suite 300
Davis, CA 95616
Lab: 530.297.4800
Fax: 530.297.4808**

Project Contact (Hardcopy or PDF To):

Rich Johnson
Company (A)

Chain-of-Custody Record and Analysis Request

Lab No. 42(5) Page 1 of 1

California EDF Report?

Sampling Company Log Code:
Recommended but not mandatory to complete this section:

1244 Pyrites Way, Gold River, CA 95670
Phone No.: Fax No.:

Project Name:	Dave's Pit Stop
Project Address:	200 Healdsburg Ave., Sebastopol,
Ex No.:	
Project Number:	(916) 851-0174
P.O. No.:	ERA02.005
File No.:	(916) 851-8541

Sample Designation
EA 95472

Remarks:

revised by:

Received by: _____

Date	Time	Received by Laboratory:	K.S.C. Analyzed
02/01/05	1430	S-DB	

Published by:



Report Number : 41838

Date : 1/10/2005

Richard Johnson
Apex Envirotech Inc.
11244 Pyrites Way
Gold River, CA 95670-4481

Subject : 3 Vapor Samples
Project Name : Dave's Pit Stop
Project Number : ERA02.005
P.O. Number : ERA02.005

Dear Mr Johnson,

Chemical analysis of the samples referenced above has been completed. Summaries of the data are contained on the following pages. Sample(s) were received under documented chain-of-custody. US EPA protocols for sample storage and preservation were followed.

Kiff Analytical is certified by the State of California (# 2236). If you have any questions regarding procedures or results, please call me at 530-297-4800.

Sincerely,

A handwritten signature in black ink that reads "Joel Kiff". The signature is fluid and cursive, with a prominent "J" at the beginning and "kiff" following it.

Joel Kiff



Report Number : 41838

Date : 1/10/2005

Project Name : **Dave's Pit Stop**Project Number : **ERA02.005**Sample : **THOXEFF**

Matrix : Air

Lab Number : 41838-01

Sample Date : 1/5/2005

Parameter	Measured Value	Method Reporting Limit	Units	Analysis Method	Date Analyzed
Benzene	< 0.050	0.050	ppmv	EPA 8260B	1/5/2005
Toluene	< 0.050	0.050	ppmv	EPA 8260B	1/5/2005
Ethylbenzene	< 0.050	0.050	ppmv	EPA 8260B	1/5/2005
Total Xylenes	< 0.050	0.050	ppmv	EPA 8260B	1/5/2005
Methyl-t-butyl ether (MTBE)	< 0.10	0.10	ppmv	EPA 8260B	1/5/2005
TPH as Gasoline	< 5.0	5.0	ppmv	EPA 8260B	1/5/2005
Toluene - d8 (Surr)	109		% Recovery	EPA 8260B	1/5/2005
4-Bromofluorobenzene (Surr)	88.9		% Recovery	EPA 8260B	1/5/2005

Sample : **THOXINF**

Matrix : Air

Lab Number : 41838-02

Sample Date : 1/5/2005

Parameter	Measured Value	Method Reporting Limit	Units	Analysis Method	Date Analyzed
Benzene	30	0.80	ppmv	EPA 8260B	1/5/2005
Toluene	190	0.70	ppmv	EPA 8260B	1/5/2005
Ethylbenzene	22	0.60	ppmv	EPA 8260B	1/5/2005
Total Xylenes	180	0.60	ppmv	EPA 8260B	1/5/2005
Methyl-t-butyl ether (MTBE)	< 0.70	0.70	ppmv	EPA 8260B	1/5/2005
TPH as Gasoline	2900	60	ppmv	EPA 8260B	1/5/2005
Toluene - d8 (Surr)	107		% Recovery	EPA 8260B	1/5/2005
4-Bromofluorobenzene (Surr)	89.2		% Recovery	EPA 8260B	1/5/2005

Approved By:

Joe Kiff

2795 2nd St , Suite 300 Davis, CA 95616 530-297-4800



Report Number : 41838

Date : 1/10/2005

Project Name : Dave's Pit Stop

Project Number : ERA02.005

Sample : VEWMAN

Matrix : Air

Lab Number : 41838-03

Sample Date : 1/5/2005

Parameter	Measured Value	Method Reporting Limit	Units	Analysis Method	Date Analyzed
Benzene	71	1.5	ppmv	EPA 8260B	1/6/2005
Toluene	370	1.5	ppmv	EPA 8260B	1/6/2005
Ethylbenzene	32	1.0	ppmv	EPA 8260B	1/6/2005
Total Xylenes	240	1.0	ppmv	EPA 8260B	1/6/2005
Methyl-t-butyl ether (MTBE)	< 1.5	1.5	ppmv	EPA 8260B	1/6/2005
TPH as Gasoline	5700	150	ppmv	EPA 8260B	1/6/2005
Toluene - d8 (Surr)	105		% Recovery	EPA 8260B	1/6/2005
4-Bromofluorobenzene (Surr)	85.6		% Recovery	EPA 8260B	1/6/2005

Approved By:

Joel Kiff

2795 2nd St., Suite 300 Davis, CA 95616 530-297-4800



**2795 2nd Street Suite 300
Davis, CA 95616**
Lab: 530.297.4800
Fax: 530.297.4808

Descriptive Statistics 111

10

卷之三

1

10

卷之三

Lab No. 411838 Page 1 of 1